



RECEIVED

JUL 6 1992

SITE ASSESSMENT SECTION



# CERCLA Screening Site Inspection Report



**Illinois Environmental  
Protection Agency**  
PO Box 19276  
Springfield, IL 62794-9276

*Confidential Material May be Enclosed*

## TABLE OF CONTENTS

INTRODUCTION	1-1
2 0 SITE BACKGROUND	2-1
2 1 INTRODUCTION	2-1
2 2 SITE DESCRIPTION	2-1
2 3 SITE HISTORY	2-4
3 0 SITE INSPECTION ACTIVITIES & ANALYTICAL RESULTS	3-1
3 1 INTRODUCTION	3-1
3 2 RECONNAISSANCE INSPECTION	3-1
3 3 SITE REPRESENTATIVE INTERVIEW	3-2
3 4 SOIL/SEDIMENT SAMPLING	3-2
3 5 GROUNDWATER SAMPLING	3-6
3 6 SURFACE WATER SAMPLING	3-8
3 7 ANALYTICAL RESULTS	3-8
3 8 KEY SAMPLES	3-9
4 IDENTIFICATION OF SOURCES	4-1
4 1 INTRODUCTION	4-1
4 2 DRUM DISPOSAL AREA	4-1
4 3 UNDERGROUND STORAGE TANKS	4-2
4 4 CONTAMINATED SOILS	4-4
4 5 LAGOON	4-5
5 MIGRATION PATHWAYS	5-1
5 1 INTRODUCTION	5-1
5 2 GROUNDWATER PATHWAY	5-1
5 3 SURFACE WATER PATHWAY	5-4
5 4 AIR PATHWAY	5-6
5 5 SOIL EXPOSURE PATHWAY	5-7

## APPENDIXES

SITE FOUR MILE RADIUS MAP	A-1
USEPA FORM 2070-13	B-1
TARGET COMPOUND LIST	C-1
IEPA PHOTOGRAPHS	D-1
WELL LOGS	E-1
ANALYTICAL RESULTS FROM IEPA COLLECTED SAMPLES	F-1

## LIST OF FIGURES

<u>Figure</u>		<u>Page</u>
2-1	STATE OF ILLINOIS LOCATION MAP	2-2
2-2	SITE LOCATION	2-3
2-3	1974 AERIAL PHOTOGRAPH	2-5
2-4	1988 AERIAL PHOTOGRAPH	2-6
2-5	SURFACE WATER ROUTE	2-9
3-1	SAMPLING LOCATIONS	3-3
3-2	SAMPLING LOCATIONS	3-4

## LIST OF TABLES

<u>Table</u>		<u>Page</u>
2-1	HISTORICAL ANALYTICAL RESULTS	2-12
3-1	SOIL SAMPLE DESCRIPTIONS	3-5
4-1	ANALYTICAL DATA FROM 1989 DRUM REMOVAL	4-1
4-2	ANALYTICAL DATA FROM 1989 OIL TANK REMOVAL	4-3
4-3	ANALYTICAL DATA FORM 1989 SOLVENT TANK REMOVAL	4-3

## 1 INTRODUCTION

On September 24, 1991 the Illinois Environmental Protection Agency's Pre-remedial Program was tasked by the U S Environmental Protection Agency (U S EPA) to conduct a screening site inspection of the Kaney Transportation, Inc facility in Rockford, Illinois

The site was initially placed on CERCLIS (Comprehensive Environmental Response and Compensation Acts Information System) in September of 1990 as a result of a request for discovery action initiated by the Illinois Environmental Protection Agency The facility received its initial CERCLA evaluation in March of 1991, when Ms Sheila Murphy of the Illinois EPA completed a formal Preliminary Assessment report In October 1991, the Illinois EPA's Pre-remedial program prepared and submitted to the Region V offices of the U S Environmental Protection Agency a screening site inspection work plan for Kaney Transportation, Inc The sampling portion of the screening site inspection was conducted on November 6 & 7 of 1991 when the inspection team collected a total of nine soil/sediment and six ground water samples The purpose of a Screening Site Inspection has been stated by U S EPA in a directive outline of Pre-Remedial program strategies The directive states

All sites will receive a screening SI to 1) collect additional data beyond the PA to enable a more refined preliminary HRS [Hazard Ranking System] score, 2) establish priorities among sites most likely to qualify for the NPL [National Priorities List], and 3) identify the most critical data requirements for the listing SI step A Screening SI will not have rigorous data quality objectives (DQOs) Based



on the refined preliminary HRS score and other technical judgement factors, the site will then either be designated as NFRAP [no further remedial action planned], or carried forward as an NPL listing candidate. A listing SI will not automatically be done on these sites, however. First, they will go through a management evaluation to determine whether they can be addressed by another authority such as RCRA (Resource Conservation and Recovery Act). Sites that are designated NFRAP or deferred to other statutes are not candidates for a Listing SI. The listing SI will address all the data requirements of the revised HRS using field screening and NPL level DQOs. It may also provide needed data in a format to support remedial investigation work plan development. Only sites that appear to score high enough for listing and that have not been deferred to another authority will receive a Listing Site Inspection (U S EPA 1988).

The Region V offices of the U S EPA have also requested that the Illinois Environmental Protection Agency identify sites during the Screening Site Inspection that may require removal action to remediate an immediate human health and/or environmental threat.

## 2 SITE BACKGROUND

### 2 1 INTRODUCTION

This section includes information obtained over the course of the formal CERCLA Screening Site Inspection investigation, and previous Illinois Environmental Protection activities involving this site

### 2 2 SITE DESCRIPTIONS

The Kaney Transportation, Inc facility is an approximately five acre site located on Cunningham Road about one and a half miles west of the city limits of Rockford, Illinois {see Figure 2-1 and 2-2} The site is found in the north half of Section 13, Township 26 North, Range 11 East of Winnebago County just west of the Third Principle Meridian The main office is situated on Meridian Road It is on the same parcel of land as the site on Cunningham Road A four mile radius map of lands surrounding the Kaney Transportation, Inc facility is provided in Appendix A of this report

Kaney Transportation, Inc is located in a small industrial area Abutting Kaney to the west is Marathon Petroleum Company Found directly north of Kaney is Cunningham Road with Torch Oil and Badger Pipeline Co beyond the road A residential area lies to the east of the site Kaney is bordered to the south by the Illinois Central Gulf Railroad line with vacant land beyond the railroad tracks

Transportation, Inc.


ord, IL

LOCATION

URE 2-1

# SITE LOCATION

## FIGURE 2-1



SOURCE: IEPA, 1992. BASE MAP: USGS, 1971 WINNEBAGO, ILLINOIS 7.5  
MINUTE QUADRANGLE

APPROXIMATE SCALE: 2 1/2" = 1 MILE

## SITE LOCATION

FIGURE 2-2

The operations at Kaney Transportation, Inc include the transportation of petroleum and resinous substances, truck maintenance and the storage of some product at the site The president of Kaney is Richard L Bell The facility is currently owned by Bell Leasing Company


The structures on site consist of a building comprised by offices in the northern portion and the shop area in the southern part, four above ground storage tanks that stand upright, and a fenced lagoon which contains two stainless steel holding tanks An estimated 1/3 of the site is covered with asphalt pavement There are also nine monitoring wells located on site (Refer to Figures 2-3 and 2-4 for site aerial photos )

### 2.3 SITE HISTORY

Until 1958 the property on which Kaney is now situated was used for agricultural purposes and owned by Russel Coffin In 1958 Mr Coffin sold part of his land to Martin Oil Services Martin Oil Services never developed this farmland

On June 15, 1983, Martin Oil deeded part of their land to Federal Land Bank Associates of Dixon According to the tax assessor, in April of 1987 the Federal Land Bank sold a parcel of land on Meridian to Richard L Bell In December 1986, Ed Kaney deeded his land on Cunningham to Richard Bell


Prior to 1988 Kaney actually consisted of two different entities Even so, both corporations had the same owners,



SOURCE IDOT, 1992 AERIAL PHOTOGRAPH

1974 AERIAL PHOTOGRAPH

FIGURE 2-3



SOURCE IDOT, 1992 AERIAL PHOTOGRAPH

1988 AERIAL PHOTOGRAPH

FIGURE 2-4

directors and officers The first was incorporated on December 12, 1946, the second June 29, 1973 Kaney Transportation, Inc was the sole subsidiary to the holding company of KTI, Inc On December 31, 1988, Kaney Transportation, Inc was merged into KTI, Inc On February 6, 1989 the name of the corporation KTI, Inc was resolved to Kaney Transportation, Inc

Operations at Kaney began between 1970 and 1971 From about January 1974 to March 1979 Kaney specialized in the transportation of a variety of liquids and gases including gasoline, fuel oil, propane, resins, asphalt, varnishes, latexes and paints During this time, Kaney washed both the interior and exterior of their trailer tanks on site According to the Division of Water Pollution Control (DWPC) files, approximately 300 gallons of wastes were released into the lagoon per week The waste water flowed from floor drains through a pipe into the holding pond located south of where the trucks were washed It was the responsibility of Kaney employees to observe the lagoon When it was full, they were to pump the waste into a tank truck to be hauled to the Rockford Sanitary District for proper disposal

In 1977 Kaney Transportation, Inc was prohibited from the Rockford Sanitary District for the disposal of effluent discharge from the on site lagoon Heavy metals and cyanide were detected in the effluent

The DWPC files indicate that the first official complaint against Kaney Transportation, Inc is recorded as being filed




before the Pollution Control Board on August 30, 1978 The complaint regarded Kaney's use of a treatment works system without a permit and lack of proper disposal methods for the contents of the lagoon

The snows of 1976-1977 and 1978-1979 made access to the lagoon difficult On different occasions Mr Robert Higgins, president of Kaney at the time, along with three citizens observed waste in the lagoon overflowing into an abutting cornfield From the cornfield the discharge flowed to a creek that lies approximately 150 feet east of the lagoon The stream flows several hundred feet to where it reaches property belonging to homeowners and flows into a private pond at approximately 1,200 feet downstream (See Figure 2-5 for the surface water route ) The liquid waste is recorded as being oily with reddish, rusty coloring and giving off "unpleasant, sickening odors"

As of March 1979, Kaney discontinued the internal washing of its trailers On December 12, 1980, the IEPA verified that Kaney had complied with settlement conditions This included installing a clay base of no less than one foot and an impermeable industrial liner covering the clay base

On November 19, 1981, the IEPA Permits Section gave Kaney permission for the installation of two stainless steel holding tanks These were placed in the lagoon and used for the storage of external wash water The IEPA was informed by Kaney in November of 1981 that Kaney qualified for the status of small quantity generator



SOURCE: IEPA, 1992. BASE MAP: USGS, 1971, ILLINOIS 7.5 MINUTE QUADRANGLE

## SURFACE WATER ROUTE

FIGURE 2-5

September 21, 1983, is the date of a report that implies Ron Bell, at that time the director of operations and personnel, was interviewed by the IEPA in regards to a complaint that a hole was dug by the complainant where the complainant saw 15-20 drums containing solvents, resins and caustic materials placed in the hole

On May 9, 1985, a RCRA inspection revealed Kaney as generating hazardous waste The hazardous waste identified was xylene Kaney had used xylene to clean their tank trailers By June 5, 1985, Kaney had shipped the 500 gallons of dirty xylene and claimed to no longer use xylene for cleaning

On June 15, 1989 the IEPA received a complaint and confirmed that Kaney Transportation, Inc was having buried drums excavated from Kaney property by Frinks Industrial Waste, Inc (FIW) FIW extracted about 40 whole drums, 30 drum fragments and ten 5-gallon buckets These were placed on plastic sheeting The majority of the barrels were found at about 14 feet below grade The excavated soil (approximately 300 yards) was stockpiled to the side

Thomas Dishno, of FIW, said the clean fill (used for backfill) was separated from the excavated area by plastic sheeting However, Thomas McNamee, of IEPA, questioned the use of plastic sheeting due to the fact that no plastic sheeting was visible in the backfill area There is also photo documentation that shows contamination to the

surrounding ground This occurred as a result of the drums being stockpiled FIW said they would remove the top layer of soil in this vicinity The following day FIW used plastic to line the hole then refilled it to grade

In June of 1989, both FIW and the IEPA took a series of soil samples On July 7, 1989, overpacking procedures began The drums containing liquids were overpacked into 20 new drums from which a composite sample was taken The solid materials were overpacked into 16 containers A composite sample was collected from the 16 drums The following contaminants were found in the composite samples Methyl Ethyl Ketone, 1,1,1-Trichloroethane, Butyl Acetate, Xylene, Naphthalene, Methanol, Toluene and Benzyl Butyl Phthalate

On July 19, 1989, three underground storage tanks (UST) were also removed from Kaney property These consisted of two 275-gallon tanks and one 550-gallon tank The two 275-gallon tanks had been installed sometime in 1970 or 1971 and were used for the storage of solvents They were located to the east of the dispatch building The 550-gallon tank was used to store waste oil It had been emplaced to the west of the dispatch building

The 275-gallon tanks were observed leaking solvent during the removal After the removal of the tanks, they were opened, the contents pumped out and the tanks were cleaned Approximately 15 drums were needed to contain the product remaining in the tanks and the wash water used for cleaning FIW and the IEPA took samples from the east and west

excavations The analytical results indicated that chlorinated solvents exist in the soil where the UST's had been

The tanks were transported to a facility for proper disposal Visqueen was placed over both excavation holes Clean backfill was used in the solvent contaminated area and brought to grade Soil contaminated with waste oil was used to bring the west excavation back to grade

In April of 1990, Mittelhauser Corporation completed sixteen soil borings and installed nine monitoring wells Over the course of the past fifteen years, there have been numerous sampling events in attempts to determine the type, amount and extent of contamination The following table is a composite list of various contaminative substances found in the above mentioned sampling events and others

TABLE 2-1

<u>VOLATILES</u>	<u>CONCENTRATIONS (PPM)</u>	<u>LOCATIONS</u>
METHYLENE CHLORIDE	91 0	Sludge in waste oil tank
ACETONE	660 0	Sludge in waste oil tank
1,2-DICHLOROETHENE	0 16	Floor of the east excavation
CHLOROFORM	460 0	Composite from solvent tank
1,2-DICHLOROETHANE	0 008	Residential Well
2-BUTANONE (MEK)	980 0	Liquid Waste
1,1,1-TRICHLOROETHANE	520 0	Composite from solvent tank
CARBON TETRACHLORIDE	980 0	Composite from solvent tank
TRICHLOROETHENE	333000 0	Composite from solvent tank

BENZENE	0 59	Monitoring Well #8
TETRACHLOROETHENE	2100 0	Composite from solvent tank
TOLUENE	28000 0	Composite from solvent tank
ETHYLBENZENE	8600 0	Composite from solvent tank
VINYL CHLORIDE	0 014	Residential Well
STYRENE	0 026	Soil, Location Unknown
XYLENE (TOTAL)	74000 0	Composite from solvent tank
CIS-1,2-DICHLOROETHANE	0 79	Monitoring Well

#### SEMIVOLATILES

PHENOLS	20900 0	Composite from solvent tank
ISOPHORONE	0 52	East excavation stockpile
NAPHTHALENE	110 0	Liquid Waste
ACENAPHTHENE	0 65	East excavation stockpile
FLUORENE	1 40	East excavation stockpile
N-NITROSODIPHENYLAMINE	1 40	East excavation stockpile
PHENANTHRENE	3 10	East excavation stockpile
DI-N-BUTYLPHTHALATE	0 37	West UST excavation
FLUORANTHENE	0 80	East excavation stockpile
PYRENE	0 80	East excavation stockpile
BUTYLBENZYLPHTHALATE	94 0	Solid Waste

#### INORGANICS

ARSENIC	9 30	Soil south of lagoon area
BARIUM	49 0	Soil pile
CADMIUM	110 0	Soil south of lagoon area
CHROMIUM	93 5	Soil south of lagoon area
COPPER	185 0	Soil south of lagoon area
IRON	2 50	Discharge east of property approx 200' SSE of lagoon

LEAD	223 0	Soil south of lagoon area
MANGANESE	0 24	Ditch approx 1000' down-stream (east) of lagoon area
MERCURY	0 022	Washwater drums
NICKEL	35 50	Soil south of lagoon area
ZINC	2550 0	Soil south of lagoon area
CYANIDE	0 96	Sludge in waste oil tank
SULFATE	28 0	Ditch approx 1000' down-
CHLORIDE	50 0	Ditch approx 200' upstream from lagoon overflow
<u>OTHERS</u>		
METHANOL	640 0	Solid Waste
BUTYL ACETATE	1100 0	Liquid Waste
ETHANOL	1 20	Washwater Drums
2-ETHOXYETHANOL ACETATE	8 90	East excavation stockpile
FLUORIDE	9 90	Discharge east of property approx 200' SSE of lagoon
PHOSPHOROUS	13 0	South edge of lagoon, 15' from southeast corner
AMMONIA	7 70	Ditch approx 200' upstream of lagoon overflow
DICHLORODIFLUOROMETHA	0 025	Boring 13

#### 2 4 APPLICABILITY OF OTHER STATUTES

This section discusses the applicability of any other environmental statutes with regards to Kaney Transportation, Inc

The facility is considered to be a small quantity generator but does not hold a permit with the IEPA under the Resource Conservation and Recovery Act (RCRA) program according to the Federal Listing of RCRA related facilities published by the Region V offices



### 3 SITE INSPECTION ACTIVITIES & ANALYTICAL RESULTS

#### 3 1 INTRODUCTION

This section outlines procedures utilized and observations made during the CERCLA Screening Site Inspection conducted at the Kaney Transportation, Inc facility. Specific portions of this section contain information pertaining to the site representative interview, reconnaissance inspection, field activities and analytical results. The Screening Site Inspection for Kaney was conducted in accordance with the site inspection work plan which was developed and submitted to the U S EPA Regional Offices prior to the initiation of field activities.

The U S Environmental Protection Agency's Potential Hazard Waste Site Inspection Report (Form 2070-13) for the Kaney Transportation, Inc site is located in Appendix B of this report.

#### 3 2 RECONNAISSANCE INSPECTION

Due to the nature of this site and the completion of a CERCLA Preliminary Assessment eight months prior to the CERCLA Screening Site Inspection, no reconnaissance inspection was conducted specifically for the SSI. During the CERCLA Preliminary Assessment reconnaissance visit the facility appeared to be well kept and clean. The lagoon was completely fenced. A small amount of liquid was observed beneath the two holding tanks in the lagoon. It was not possible to determine if the liquid originated from rain.



water or possibly a leak from the tanks


### 3.3 SITE REPRESENTATIVE INTERVIEW

On November 6, 1991, the IEPA sampling team, consisting of Sheila Murphy, Ken Corkill, Greg Dunn and Kim Nika, arrived at the Kaney Transportation, Inc facility at approximately 10 20 AM At that time the team met with Michelle Susic of Mittelhauser Corporation, a representative of Kaney Mr Bell, president of Kaney, arrived approximately ten minutes following At this time there was an informal meeting during which Mr Bell mentioned that Marathon Oil had recently put in wells, probably monitoring wells

The following day Mr Roger Theille, a Kaney employee, mentioned that Kaney's on site well was supplying the non-responsive home with water until the non-responsive had the new well installed

### 3 4 SOIL/SEDIMENT SAMPLING

On November 7, 1991, Illinois Environmental Protection Agency (IEPA) personnel collected the nine soil/sediment samples (see Figures 3-1 and 3-2 for locations) on site and in the proximity of the site within areas of suspected contamination The main objective of these soil/sediment samples was to determine if any U S EPA Target Compound List (TCL) contaminants were present at the site or at potential receptors of concern (The Target Compound List is provided in Appendix C of this report ) This would aid in the delineation of the extent of potential contamination The following table details individual samples with their



# SAMPLING LOCATIONS

FIGURE 3-1

non-responsive

locations, depths and physical appearances (Refer to the analytical data in Appendix F for detection limits associated with each sample point )

TABLE 3-1  
Soil Sample Descriptions

<u>Sample</u>	<u>Depth</u>	<u>Appearance</u>	<u>Location</u>
X101	0-6"	Dark silty clay	West boundary of Kaney property
X102	1-4"	Black nondescript humous/topsoil	Southwest corner of <span>non-responsive</span> backyard
X103	0-6"	Brownish-black topsoil	East of South Weldon Rd north of R R tracks & west of barbed wire fence
X104	6"-2'	Very sandy with clay, had waste oil-like odor	Lagoon area
X105	0-4"	Brown Clay with sand & gravel	3' north of gas pipe south of Kaney's southern boundary
X106	0-4"	Brown silty clay with sand and some gravel	22'11" south of southern lagoon boundary 75'9" east of east boundary fence of site
X107	0-2"	Clay with fine brown sand and some pebbles	Southwest corner of Cunningham Rd and Meridian Rd west of culvert
X108	4"-8"	Very black with organic matter	East end of <span>non-responsive</span> pond
X109	0-2"	Black with organic matter	West end of <span>non-responsive</span> pond

The above soil/sediment samples were taken with stainless steel spoons and bucket augers. Decontamination of equipment was done at the IEPA's warehouse prior to and following the SSI. Decontamination procedures include the cleaning of the equipment with liquidalconex and warm water, rinsing with tap water, rinsing with a 50% acetone 50% distilled water mixture, rinsing with warm tap water and a final rinsing of distilled water. The spoons and augers dried on paper towels and were wrapped in aluminum foil.

### 3.5 GROUNDWATER SAMPLING

Sampling was conducted November 6 & 7, 1991 by the screening site inspection team. Illinois EPA personnel took a total of six groundwater samples, four of which were from on site monitoring wells and two from privately owned wells.

The four on site monitoring wells were purged manually with the use of teflon bailers. Temperature, pH and specific conductivity readings were taken prior to sampling wells G101, G104 and G109.

It should be noted that when the water level indicator was placed in monitoring well G102, the instrument's buzzer did not sound until it had passed through the top layer of the well contents. Because the water level indicator is constructed to read water levels (as opposed to something like Benzene levels) and did not buzz when initially penetrating the well contents, it was believed the well water

had product floating on top The HNU reading for this well registered at 300 units above background When the water was bailed out there was what appeared to be a petroleum type product floating on the surface Temperature, pH and specific conductivity readings were not administered to monitoring well G102 due to potential damage to instrumentation

Sample G202 was taken from a residential well owned by the [non-responsive] This well is located approximately 1/4 mile to the northeast of Kaney Transportation, Inc The sample was taken in the basement of the [non-responsive] home The water softener was turned off The water was allowed to run for approximately 15 minutes prior to sampling A series of three readings of temperature, pH and conductivity were taken

Sample G203 was extracted from a residential well owned by the [non-responsive] The water was taken from a spigot located on the outside of the house The water was purged for approximately 15 minutes before sampling began G203 is situated approximately 850 feet to the westnorthwest of Kaney Transportation, Inc Temperature, pH and conductivity readings were taken for this sample, also

One other well, belonging to the [non-responsive], had originally been on the agenda to sample However, at the time of the CERCLA SSI this well was out of commission

Preservatives were added to the appropriate inorganic bottles after the sampling bottles were filled for each of the above mentioned groundwater samples Locations of these

wells can be found on Figures 3-1 and 3-2

Teflon bailers and new nylon cord were used to sample all monitoring wells. Decontamination of equipment was done at the IEPA's warehouse prior to and following the SSI. Decontamination procedures include the cleaning of bailers with liquidalconex and warm water, rinsing with tap water, rinsing with a 50% acetone 50% distilled water mixture, rinsing with warm tap water and a final rinsing of distilled water. The bailers dried on paper towels and were wrapped in aluminum foil.

### 3.6 SURFACE WATER SAMPLING

There were no surface water samples taken during the CERCLA Screening Site Inspection for Kaney Transportation. Sediment sampling was chosen instead of surface water sampling for the unnamed creek and residential pond.

### 3.7 ANALYTICAL RESULTS

Chemical analysis of groundwater samples collected from the two private wells revealed the presence of both organic and inorganic compounds and suspected laboratory artifacts. Analysis of the soil/sediment samples collected at the facility and off site indicated the existence of volatiles, semi-volatiles, inorganic compounds, suspected laboratory artifacts and common soil/sediment constituents.

See the Sample Summary Table for the summary of the groundwater and soil/sediment sample results. The Sample Summary Table and complete laboratory analytical data of

these results can be found in Appendix F of this report

### 3.8 KEY SAMPLES

Table 3-2 identifies those samples taken during the CERCLA Screening Site Inspection (SSI) which were shown to contain contaminants at a level significantly higher than the background concentrations

For the review of all contaminants detected in samples taken during the CERCLA SSI, the reader is referred to the Sample Summary Table located in the front of Appendix F of this report



TABLE 3-2

## KEY SAMPLES

SAMPLING POINT	X 103 11-7-91	X 101 11-7-91	X 104 11-7-91	X 105 11-7-91	X 106 11-7-91	X 107 11-7-91	X 109 11-7-91	X 108 11-7-91	X 102 11-7-91	G 203 11-7-91	G 104 11-6-91	G 102 11-6-91	G 108 11-6-91	G 101 11-6-91	G 202 11-6-91	TRIP BLANK
PARAMETER																
<b>VOLATILES</b>	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB
Chloromethane	---	---	---	---	---	---	---	---	---	---	---	1900.0	---	---	---	---
Vinyl Chloride	---	---	---	---	---	---	---	---	---	---	---	---	---	30.0	---	---
Acetone	---	---	---	---	---	---	---	---	---	---	---	19000.0 BJ	---	---	---	31.0
1,2-Dichloroethane (total)	---	---	---	---	---	---	---	---	---	---	---	---	31.0	120.0 D	40.0	---
1,2-Dichloroethane	---	---	---	---	---	---	---	---	---	---	---	---	---	21.5	---	---
Trichloroethene	---	---	---	52.0	30.0	---	---	---	---	---	---	---	23.0	91.0 D	10.0	---
Tetrachloroethene	---	---	---	---	---	---	---	---	---	---	---	---	---	16.5	---	---
Toluene	---	---	---	---	---	---	---	---	---	---	---	6100.0 J	---	---	---	---
<b>SEMIVOLATILES</b>	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB
Naphthalene	---	---	---	---	---	---	---	---	---	---	140.0 D	1200.0	---	---	---	---
2-Methylnaphthalene	---	---	---	---	---	---	---	---	---	---	32.0 D	4800.0	---	---	---	---
Phenanthrene	---	---	---	---	---	1400.0	---	780.0	---	---	---	1300.0	---	---	---	---
Fluoranthene	---	---	---	---	---	1800.0	---	1000.0	---	---	---	---	---	---	---	---
Pyrene	---	---	---	---	---	1700.0	---	650.0	---	---	---	---	---	---	---	---
Benzo(a)anthracene	---	---	---	---	---	1000.0	---	---	---	---	---	---	---	---	---	---
Chrysene	---	---	---	---	---	950.0	---	---	---	---	---	---	---	---	---	---
Benzo(b)fluoranthene	---	---	---	---	---	1200.0	---	---	350.0 J	---	---	---	---	---	---	---
Benzo(k)fluoranthene	---	---	---	---	---	580.0	---	---	---	---	---	---	---	---	---	---
Benzo(a)pyrene	---	---	---	---	---	800.0	---	---	---	---	---	---	---	---	---	---
<b>INORGANICS</b>	PPM	PPM	PPM	PPM	PPM	PPM	PPM	PPM	PPM	PPB	PPB	PPB	PPB	PPB	PPB	PPB
Aluminum	8930.0	9470.0	5880.0	7440.0	8930.0	7320.0	5830.0	9890.0	11200.0	---	14200.0	30000.0	12300.0	14800.0	---	---
Antimony	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---
Barium	152.0 J	278.0 J	5670.0 J	105.0 J	151.0 J	102.0 J	89.50	138.0 J	305.0	---	300.0	300.0	210.0	---	---	---
Calcium	---	---	23400.0 J	9.90	24.40	11.90	18.80	13.0	---	---	---	---	---	---	---	---
Cobalt	---	13.80	---	---	---	---	---	---	---	---	---	---	---	---	---	---
Copper	---	---	---	---	---	---	---	---	---	---	285.0	178.0	---	---	---	---
Magnesium	---	---	13600.0 J	---	---	---	---	---	---	---	---	---	---	---	---	---
Manganese	---	---	---	---	---	---	---	---	---	---	3320.0	4520.0	1850.0	1040.0	963.0	---
Mercury	0.10	---	---	---	---	---	---	---	0.670	---	---	---	---	---	---	---
Nickel	---	---	---	---	---	---	---	---	---	---	450.0	397.0	---	31.0	---	---
Potassium	---	---	---	---	---	---	---	---	---	---	18300.0	18500.0	12600.0	23100.0	---	---
Sodium	---	---	---	---	---	---	---	---	---	---	---	---	22800.0	---	31500.0	---
Vanadium	---	---	---	---	---	---	---	---	---	---	54.0	71.0	---	---	15.0	---
Zinc	---	---	---	---	---	---	---	---	---	---	112.0	206.0	---	---	---	---
Cyanide	---	---	2.30	---	---	---	---	---	---	---	---	---	---	---	---	---
Sulfur	---	---	52.10	---	132.0	154.0	107.0	613.20	---	---	---	---	---	---	---	---
Sulfide	---	---	---	---	---	---	---	---	---	---	---	---	6860.0	9130.0	6290.0	---
<b>TENTATIVELY IDENTIFIED COMPOUNDS</b>	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB	PPB
Benzaldehyde	---	---	---	270.0	330.0	530.0	---	820.0	---	---	4.0	---	---	---	---	---
Benzo(b)Thiophene	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---
1,3,5-Cycloheptatriene	---	---	---	---	---	---	830.0	---	---	---	---	---	---	---	---	---
Cyclohexane	---	---	---	---	---	---	---	---	---	---	---	---	---	14.0	---	---
1-Ethyl-3-Methyl-Benzene	---	---	---	---	---	---	---	---	---	---	---	23000.0	---	---	---	---
3-Methyl-3-Buten-2-One	---	---	---	410.0	530.0	1800.0	1100.0	---	---	---	---	---	---	---	---	---
Methyl Cyclopentane	---	---	---	---	---	---	---	---	---	---	---	---	---	23.0	---	---
3-Methyl-Hexane	---	---	---	---	---	---	---	---	---	---	---	650.0	---	---	---	---
Undecane	---	---	---	---	---	---	---	---	---	---	---	5200.0	---	---	---	---

## 4 IDENTIFICATION OF SOURCES

### 4 1 INTRODUCTION

This section discusses the various hazardous waste sources which have been identified in the initial stages of the CERCLA site investigation

Information concerning the size, volume and waste composition of each source has been derived throughout the initial site assessment and the screening site inspection sampling action. It should be pointed out however, that the total number and nature of each of the sources identified below may be subject to change, as the site progresses through the CERCLA site investigation program and receives further investigation

### 4 2 DRUM DISPOSAL AREA

In June of 1989, Kaney had employed Frinks Industrial Waste, Inc (FIW) to excavate some buried drums. The excavation took place on the southwestern side of Kaney's property. Approximately 40 complete drums, 30 drum fragments and ten 5-gallon buckets were found in this area.

The following table displays some of the organic compounds that were revealed through a series of analytical results. These samples were taken in June and July of 1989 in correlation to the drum excavation.

TABLE 4-1

<u>Compound</u>	<u>Concentration</u>	<u>Location</u>
Methylene Chloride	0.008 PPM	Soil Boring

1,2-Dichloroethane	0 005	PPM	Soil Boring
Ethyl Benzene	0 014	PPM	Soil Boring
Dichlorodifluorometha	0 025	PPM	Soil Boring
Acetone	0 85	PPM	Soil Pile
Methyl Ethyl Ketone	980 0	PPM	Composite liquid sample from drums
1,1,1-Trichloroethane	70 0	PPM	Composite liquid sample from drums
Butyl Acetate	1100 0	PPM	Composite liquid sample from drums
Xylene	200 0	PPM	Composite liquid sample from drums
Naphthalene	110 0	PPM	Composite liquid sample from drums
Methanol	640 0	PPM	Composite solid waste sample from drums
Toluene	40 0	PPM	Composite solid waste sample from drums
Benzyl Butyl Phthalate	94 0	PPM	Composite solid waste sample from drums

#### 4.3 UNDERGROUND STORAGE TANKS

Three underground storage tanks were removed from the Kaney Transportation, Inc facility in July of 1989. The removal consisted of one 550-gallon tank and two 275-gallon tanks.

The 550-gallon tank had been buried on the west side of the dispatch building. It had been employed to store waste oil. Table 4-2 highlights the contaminants derived from samples taken in July of 1989 during this excavation.

TABLE 4-2

<u>Compound</u>	<u>Concentration</u>	<u>Location</u>
Tetrachloroethene	0 008 PPM	West excavation
Benzyl Butyl Phthalate	1 70 PPM	West excavation
Di-n-Butylphthalate	0 37 PPM	West excavation
Phenanthrene	2 40 PPM	Floor of west excavation
Methylene Chloride	91 0 PPM	Sludge in waste oil tank
Acetone	660 0 PPM	Sludge in waste oil tank
Trichloroethene	180 0 PPM	Sludge in waste oil tank
Toluene	440 0 PPM	Sludge in waste oil tank
Ethylbenzene	880 0 PPM	Sludge in waste oil tank
Xylene	3200 0 PPM	Sludge in waste oil tank

The two 275-gallon tanks were removed from the opposite side of the dispatch building. These tanks had been storing solvent. They were installed sometime in 1970 or 1971 and used until the mid to late 70's. These tanks were observed leaking their contents during removal.

The following table denotes some of the organic compounds that were found during the excavation of the solvent tanks.

TABLE 4-3

<u>Compound</u>	<u>Concentration</u>	<u>Location</u>
Methanol	0 092 PPM	Stockpile east excavation
2-Ethoxyethanol Acetate	8 90 PPM	Stockpile east excavation
Acenaphthene	0 65 PPM	Stockpile east excavation
Fluoranthene	0 80 PPM	Stockpile east excavation

Fluorene	1	40	PPM	Stockpile east excavation
Isophorone	0	52	PPM	Stockpile east excavation
N-Nitrosodiphenylamine	1	40	PPM	Stockpile east excavation
Phenanthrene	3	10	PPM	Stockpile east excavation
Pyrene	0	80	PPM	Stockpile east excavation
1,2-Dichloroethene	0	16	PPM	Floor of east excavation
Acetone	2	60	PPM	Stockpile east excavation
Trichloroethene	330000	0	PPM	Composite from east tanks
Toluene	28000	0	PPM	Composite from east tanks
Xylene	74000	0	PPM	Composite from east tanks
Methylene Chloride	>250	0	PPM	Composite from east tanks
Chloroform	460	0	PPM	Composite from east tanks
1,1,1-Trichloroethane	520	0	PPM	Composite from east tanks
Carbon Tetrachloride	980	0	PPM	Composite from east tank
Tetrachloroethene	2100	0	PPM	Composite from east tanks
Ethylbenzene	8600	0	PPM	Composite from east tanks

There was no sampling done from the tank areas during the CERCLA Screening Site Inspection because of former excavations

#### 4.4 CONTAMINATED SOILS

Due to the fact that Kaney Transportation, Inc has a history of buried drums and tanks, there exists the potential of contaminated soils on site. In the 1989 excavations, known containers and approximately 300 yards of contaminated soils were removed. However, records indicate that several of these containers were in poor condition and were leaking

Records also imply that not all of the contaminated soils were removed. Although the on site soil sample from the CERCLA SSI showed nondetect for VOC's, there remains a potential for contaminated soils on Kaney property.

#### 4.5 LAGOON

Aerial photographs show the presence of the on site lagoon as early as April of 1974 (see Figure 2-3 for aerial photograph). Until March of 1979, the lagoon was used to contain the waste wash water that had been used to clean both the exterior and interior of the facility's trucks. These trucks had carried substances such as gasoline, fuel oil, propane, resins, asphalt, varnishes, latexes and paints.

IEPA records indicate that approximately 300 gallons of wastes were released into the lagoon per week. The lagoon measures approximately 100'x100'x8'. At different times the lagoon was observed overflowing. The effluent made its way downstream to a private pond located approximately 1,200 feet downstream. In March of 1979, Kaney discontinued the internal washing of its trailers. In November of 1981, the

IEPA Permits Section gave Kaney Transportation permission for the installation of two stainless steel holding tanks. Instead of the lagoon holding the external wash water, the tanks would contain it. The tanks were placed in the lagoon area. Sample X104 was taken from the floor of the lagoon at a depth of 6 inches to 2 feet deep. Sampling at a deeper level was not carried out due to the fact that the lagoon

supposedly has a clay base with an impermeable industrial liner covering the clay base. Disruption of this layer could have brought forth a worse case scenario for this site. Because of this, potential hazardous contaminants lying below the liner were unattainable.

## 5 MIGRATION PATHWAYS

### 5 1 INTRODUCTION

This section includes information that may be useful in analyzing the Kaney Transportation, Inc facility's impact on the four migration pathways identified in CERCLA's hazard ranking system (HRS) The migration pathways which will be analyzed in this section include groundwater, surface water, air and soil exposure

### 5 2 GROUNDWATER PATHWAY

The Quarternary System of Winnebago County, approximately 20 feet thick, is constituted by emplacements of the Wisconsinan Cahokia Alluvium and Illinoian Argyle Till According to the Handbook of Illinois Stratigraphy (published in 1975) the absence of the Silurian and Maquoketa Group in this region is attributable to erosion Beneath the Quarternary System lie dolomites of the Galena and Platteville Groups The Ancell Group is the base of the Ordovician System It is made up of a thin layer of the Glenwood Formation overlying the St Peter Sandstone Next in the stratigraphic column is the Cambrian System This consists of Potosi, Franconia, Iron-ton-Galesville, Eau Claire and the Mt Simon Formation At approximately 2,650 feet below the surface lies the Precambrian basement

Kaney Transportation, Inc property's elevation ranges from approximately 812 to 821 feet above mean sea level Sitting atop the Galena Platteville Group lie the surface



soils down to approximately 10 feet which consist of silty clays. However, not as much clay is found near the southern end of the facility because of erosion. It is not uncommon to find a moist to wet sand layer adjacent to the surficial soils. Silt is the primary ingredient from 10 feet to about 28 feet. For the next six feet the loam turns sandy and contains clay, silt, gravel and cobbles.

Regional well logs document drinking wells using water at depths ranging anywhere from 34 to 308 feet deep. However, because available documentation indicates this aquifer does not have a confining layer, it may be considered a continuous aquifer.

The nearest municipal well lies less than two miles away. This public well serves the city of Rockford.

Residents and private industries in the area of Kaney use drive water from private wells. The Kaney facility on Cunningham has a deep well that is used for drinking water. This well was installed in the fall of 1991. Use of drinking water from the original well was discontinued due to contamination.

The closest residential well belongs to the [non-responsive]. It lies approximately 50' east of the Kaney facility. In January of 1986, the Illinois Department of Public Health (IDPH) sampled two residential private wells for volatile inorganic compounds (VOC's) and the Winnebago County Health Department (WCHD) sampled four private residential wells and two industrial wells for purgeable organic carbons (POC) and

purgeable organic halides (POX) Following the sampling, WCHD recommended to the four residential owners that water sources other than their own wells should be used During a meeting in March of 1986, several of the neighboring petroleum companies agreed to supply bottled water to the residents with contaminated wells Each of the residential homes was supplied with 18 gallons of water per every two weeks

In October of 1991 a PRP (potentially responsible party)-group, Kaney inclusive, began the installation of new private wells into the St Peter Sandstone in attempts to provide safe drinking water to the residents with contaminated wells

The first of these wells installed was at the [non-responsive] residence Five consecutive weekly samplings indicated that there were no volatile organic compounds (VOC's) above detection limits

The next well installed was at the [non-responsive] residence This residence is found at the northeast corner of the intersection of Cunningham Road and Meridian Road This well was completed in the St Peter Sandstone Analytical results showed much higher levels of VOC's in the new well than in the shallow well at this location

An IEPA source indicated that following the sampling of the [non-responsive] new deep well and the discovery of contamination, the PRP-group decided to not install any more of the residential wells Currently, the PRP-group is proposing to buy the [non-responsive] and possibly the [non-responsive]

properties

During the November 1991 CERCLA SSI for Kaney, samples were taken from four onsite monitoring wells and two residential wells (see Figures 3-1 and 3-2 for locations) The [non-responsive] well was to be sampled from also, but this was not possible at the time of the sampling event

Analytical data from the on site monitoring wells shows the presence of inorganic compounds that were detected at three times above background, volatiles, semivolatiles and TIC's (tentatively identified compounds) Analytical results from samples G202 and G203 (the residential wells) indicate the occurrence of four compounds also found in the on site monitoring wells These include the following Toluene, Benzene, Trichloroethene and 1,2-Dichloroethene(total)

Sample G203 was taken from the [non-responsive] well The analytical results registered Trichloroethene at 10 PPB The MCL (maximum contaminant level) for Trichloroethene is 5 PPB The MCL for Benzene is 5 PPB This sample indicated Benzene as being at a level of 6 PPB One other volatile, 1,2-Dichloroethene, was found in sample G203 at 40 PPB The MCL for this compound is 70 PPB

### 5.3 SURFACE WATER PATHWAY

Approximately 100' east of the lagoon area is an unnamed creek This stream flows approximately 400 yards downstream to a private pond, known as Zander's Pond, owned by the

[non-responsive]

Prior to indications of contamination,

the pond had been used for fishing and boating. Contamination was determined because of the odd tasting fish, the discoloration of the pond (which originated from the unnamed creek) and a large number of dead fish. This is where the overflows from the lagoon discharged into in the late 1970's.

From Zander's Pond the creek continues flowing in a northeasterly direction until it runs into the North Fork Kent Creek. This creek flows to the south for approximately 260 yards at which point it turns east. The North Fork Kent Creek flows directly into Levings Lake. After leaving Levings Lake this water body feeds into the Rock River. Refer to Figure 2-5 for the surface water route. According to Richard Lutz, of the Illinois Department of Conservation (IDOC), the Rock River supports a fishery for important game fish species. The Rock River is classified as a Highly Valued Aquatic Resource. Any discharge or runoff from the site could pose a threat to these natural resources. There are no surface water intakes documented within 15 miles downstream of the surface water route.

The sensitive environments of concern for the Kaney Transportation, Inc. site include the wetlands of the area. According to Soil Conservation Service (SCS) maps, there are approximately 11 acres of wetlands within a 1/4 mile radius of Kaney and 25 acres of wetlands between a 1/4 mile and 1/2 mile radius of Kaney. Wetlands are also found along the 15-mile surface water pathway.

During the November 1991 CERCLA SSI three sediment

samples were taken from the unnamed creek and two sediment samples were taken from the pond. Results of samples X105 and X106, taken from the unnamed creek, revealed the presence of Trichloroethene. Analytical data from sample X107, also taken from the unnamed creek, documents the presence of several semivolatiles, six which are carcinogenic PNA's (polynuclear aromatic hydrocarbons). The samples taken from the pond indicate the occurrence of volatile and semivolatile contaminants. Four of these contaminants found in X109 are carcinogenic PNA's. Locations of the aforementioned samples can be found in Figure 3-2 of this report.

Kaney Transportation, Inc. is located outside of the 500 year flood boundary according to the National Flood Insurance Rate Maps.

#### 5.4 AIR PATHWAY

During the CERCLA Screening Site Inspection, no documented releases to the air were observed. A photo-ionization detector (HNU) with an 11.7 eV lamp was used to determine the presence of certain airborne contaminants. The HNU was used at various locations during soil/sediment and groundwater sampling activities. While bailing monitoring well G102, the HNU read at a level of 300 units. Due to the enhanced potential of inhaling contaminants from the breathing zone, samplers put on respirators and then resumed sampling procedures.

Although the two on site soil samples may indicate that a

threat for windblown particulates to be carried off site is negligible, historical records document the presence of contaminated soils on site and therefore should be considered a possibility

#### 5.5 SOIL EXPOSURE PATHWAY

Soil/Sediment samples collected during the Screening Site Inspection suggest a potential for direct contact with hazardous constituents. The Kaney facility has an approximately seven foot high chain-link fence that runs along the western and northern perimeters of the facility. The north fence has a gate incorporated into it which is used for entrance onto Kaney property. The eastern perimeter has a wooden fence running approximately a quarter of the way down from Cunningham Road. The southern perimeter has a wire fence that is approximately three feet high. The lagoon area is completely enclosed by a chain-link fence.

There are approximately five people that work at the Kaney facility. Two of these are Kaney employees. The other three work for a company that rents space from Kaney. There are also approximately six truck drivers that work for Kaney which are occasionally on site.

Samples X101 and X104 were the two onsite soil samples. These samples showed nondetect for VOC's. Nonetheless, the historical records document the presence of contaminated soils on site. Thus, the soil pathway should be considered as a potential source of contamination to those on site.


## 6 BIBLIOGRAPHY

- Illinois Environmental Protection Agency, 1990, Potential Hazardous Waste Site Preliminary Assessment for Kaney Transportation, Inc , ILD064006901, prepared by Sheila Murphy, Springfield, IL
- Illinois State Geological Survey, 1956, Groundwater in Northwestern Illinois, Circular 207
- Illinois State Geological Survey, 1975, Handbook of Illinois Stratigraphy, Bulletin 95
- U S Census Bureau, 1990, Average persons-per-household in Lake County, Illinois
- U S Department of Housing and Urban Development, 1980, Flood Insurance Rate Map, Winnebago County, Illinois
- U S G S , 1971, Kishwaukee, IL Quadrangle, 7 5 Minute Series
- U S G S , 1971, Rockford North, IL Quadrangle, 7 5 Minute Series
- U S G S , 1971, Rockford South, IL Qudrangle, 7 5 Minute Series
- U S G S , 1971, Winnebago, IL Quadrangle, 7 5 Minute Series

**APPENDIX A**

**SITE FOUR MILE RADIUS MAP**





ILLINOIS ENVIRONMENTAL PROTECTION AGENCY		SITE NAME: Kishwaukee Transportation SITE ID: D44006901.....	
USGS TOPOGRAPHIC MAPS			
NAME: Winnebago	NAME: Rockford North	 LEGEND	
DATE: 1971	DATE: 1971		
REVISED: 1976	REVISED: 1976		
NAME: Kishwaukee	NAME: Rockford South		
DATE: 1971	DATE: 1971		
REVISED: 1976	REVISED: 1976		
MAP SCALE: 1 inch = 1 mile			



**APPENDIX B**

**U S EPA FORM 2070-13**



# Site Inspection Report



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 1 SITE LOCATION AND INSPECTION INFORMATION

I IDENTIFICATION  
01 STATE 02 SITE NUMBER  
IL D064006901

II SITE NAME AND LOCATION

01 SITE NAME (Legal, common or descriptive name of site) Nancy Transportation Inc	02 STREET ROUTE NO OR SPECIFIC LOCATION IDENTIFIER 7222 Cunningham Road
03 CITY Rockford	04 STATE 05 ZIP CODE 06 COUNTY IL 61102 Winnebago
07 COUNTY CODE 08 CONG DIST 201 IL-16	
09 COORDINATES LATITUDE 89° 10' 39" - LONGITUDE -42° 15' 35" -	10 TYPE OF OWNERSHIP (Check one) <input checked="" type="checkbox"/> A. PRIVATE <input type="checkbox"/> B. FEDERAL <input type="checkbox"/> C. STATE <input type="checkbox"/> D. COUNTY <input type="checkbox"/> E. MUNICIPAL <input type="checkbox"/> F. OTHER <input type="checkbox"/> G. UNKNOWN

III INSPECTION INFORMATION

01 DATE OF INSPECTION 11, 6, 91 MONTH DAY YEAR	02 SITE STATUS <input checked="" type="checkbox"/> ACTIVE <input type="checkbox"/> INACTIVE	03 YEARS OF OPERATION 1971-2 present BEGINNING YEAR ENDING YEAR
04 AGENCY PERFORMING INSPECTION (Check all that apply) <input checked="" type="checkbox"/> A. EPA <input type="checkbox"/> B. EPA CONTRACTOR (Name of firm) <input type="checkbox"/> C. MUNICIPAL <input type="checkbox"/> D. MUNICIPAL CONTRACTOR (Name of firm) <input type="checkbox"/> E. STATE <input type="checkbox"/> F. STATE CONTRACTOR (Name of firm) <input type="checkbox"/> G. OTHER (Specify)		

05 CHIEF INSPECTOR Sheila Murphy	06 TITLE Life Science Career Trainee	07 ORGANIZATION IEPA	08 TELEPHONE NO (217) 782-6760
09 OTHER INSPECTORS Greg Duan	10 TITLE Environmental Protection Specialist	11 ORGANIZATION IEPA	12 TELEPHONE NO (217) 782-6760
Ken Corkill	Environmental Protection Specialist	IEPA	(217) 782-6760
Kim Nika	Environmental Protection Specialist	IEPA	(217) 782-6760
			( )
			( )

13 SITE REPRESENTATIVES INTERVIEWED Michelle Susic / Mittelhauser Corp	14 TITLE Staff Geologist	15 ADDRESS 60543 1240 Indigois Naperville, IL	16 TELEPHONE NO (708) 369-0201
Richard Bell	President	1515 S. Meridian Rockford	(815) 962-4026
			( )
			( )
			( )
			( )

17 ACCESS GAINED BY (Check one) <input checked="" type="checkbox"/> PERMISSION <input type="checkbox"/> WARRANT	18 TIME OF INSPECTION 10 20 AM	19 WEATHER CONDITIONS Cloudy, windy + Cold ~ 15°
--	-----------------------------------	---

IV INFORMATION AVAILABLE FROM

01 CONTACT Michelle Susic	02 OF (Agency/Organization) Mittelhauser Corporation	03 TELEPHONE NO (708) 369-0201
04 PERSON RESPONSIBLE FOR SITE INSPECTION FORM Sheila Murphy	05 AGENCY IEPA	06 ORGANIZATION RPM2
	07 TELEPHONE NO (217) 782-6760	08 DATE 11 6-7, 91 MONTH DAY YEAR



01 STATE	02 SITE NUMBER
IL	D064D06901

<b>01 PHYSICAL STATES</b> ( <i>Check all that apply</i> ) <input checked="" type="checkbox"/> A SOLID <input type="checkbox"/> B POWDER FINES <input checked="" type="checkbox"/> C SLUDGE  <input type="checkbox"/> D OTHER _____ ( <i>Specify</i> )	<b>02 WASTE QUANTITY AT SITE</b> ( <i>Measures of waste quantities must be independent</i> )  <div style="text-align: center;">TONS _____</div> <div style="text-align: center;">CUBIC YARDS _____</div> <div style="text-align: center;">NO OF DRUMS _____</div>	<b>03 WASTE CHARACTERISTICS</b> ( <i>Check all that apply</i> ) <div style="display: flex; justify-content: space-between;"> <div style="width: 30%;"> <input checked="" type="checkbox"/> A. TOXIC  <input type="checkbox"/> B. CORROSIVE  <input type="checkbox"/> C. RADIOACTIVE  <input type="checkbox"/> D. PERSISTENT           </div> <div style="width: 30%;"> <input type="checkbox"/> E. SOLUBLE  <input type="checkbox"/> F. INFECTIOUS  <input type="checkbox"/> G. FLAMMABLE  <input type="checkbox"/> H. KNITABLE           </div> <div style="width: 30%;"> <input type="checkbox"/> I. HIGHLY VOLATILE  <input type="checkbox"/> J. EXPLOSIVE  <input type="checkbox"/> K. REACTIVE  <input type="checkbox"/> L. INCOMPATIBLE  <input type="checkbox"/> M. NOT APPLICABLE           </div> </div>
---	--	--

CATEGORY	SUBSTANCE NAME	01 GROSS AMOUNT	02 UNIT OF MEASURE	03 COMMENTS
SLU	SLUDGE	Unknown		1989 excavation, 2
OLW	OILY WASTE			375 gallon tanks, 1 550
SOL	SOLVENTS			gallon tank, ~40 whole
PSD	PESTICIDES			drums, 30 drum fragments,
OCC	OTHER ORGANIC CHEMICALS			10 5 gallon buckets & ~300
IOC	INORGANIC CHEMICALS			yards of contaminated soil
ACD	ACIDS			were removed
BAS	BASES			
MES	HEAVY METALS			

01 CATEGORY	02 SUBSTANCE NAME	03 CAS NUMBER	04 STORAGE/DISPOSAL METHOD	05 CONCENTRATION	06 MEASURE OF CONCENTRATION

# SEE SAMPLE SUMMARY

## TABLE IN APPENDIX F

CATEGORY	01 FEEDSTOCK NAME	02 CAS NUMBER	CATEGORY	01 FEEDSTOCK NAME	02 CAS NUMBER
FDS			FDS		
FDS			FDS		
FDS			FDS		
FDS			FDS		

IEPA Bureau of Land Files  
IEPA Division of Water Files  
CERCLA Site Inspection Analytical Results  
SSI Conducted November 6 & 7, 1991



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT

PART 3 DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE 02 SITE NUMBER  
IL D064006901

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☒ A GROUNDWATER CONTAMINATION w/ 4 miles 02 ☒ OBSERVED (DATE \_\_\_\_\_) ☐ POTENTIAL ☐ ALLEGED  
03 POPULATION POTENTIALLY AFFECTED ~41,000 04 NARRATIVE DESCRIPTION

Since January of 1986 there has been known contamination to ground water in the vicinity of the site. Samples taken from Kaney monitoring wells in 1990 documented contamination at the site. The 1991 CERCLA SSI indicated contamination on + off site.

01 ☒ B SURFACE WATER CONTAMINATION 02 ☒ OBSERVED (DATE \_\_\_\_\_) ☐ POTENTIAL ☐ ALLEGED  
03 POPULATION POTENTIALLY AFFECTED 04 NARRATIVE DESCRIPTION

Sediment samples indicate contamination to an unnamed creek + a residential pond (contamination may extend further than this)

01 ☐ C CONTAMINATION OF AIR 02 ☐ OBSERVED (DATE \_\_\_\_\_) ☐ POTENTIAL ☐ ALLEGED  
03 POPULATION POTENTIALLY AFFECTED 04 NARRATIVE DESCRIPTION

None documented or observed

01 ☐ D FIRE/EXPLOSIVE CONDITIONS 02 ☐ OBSERVED (DATE \_\_\_\_\_) ☐ POTENTIAL ☐ ALLEGED  
03 POPULATION POTENTIALLY AFFECTED 04 NARRATIVE DESCRIPTION

None documented or observed

01 ☒ E DIRECT CONTACT 02 ☐ OBSERVED (DATE \_\_\_\_\_) ☐ POTENTIAL ☐ ALLEGED  
03 POPULATION POTENTIALLY AFFECTED 04 NARRATIVE DESCRIPTION

In 1989 soils were excavated from the Kaney facility. Records imply that contaminated soil may still exist on site.

01 ☒ F CONTAMINATION OF SOIL 02 ☐ OBSERVED (DATE \_\_\_\_\_) ☐ POTENTIAL ☐ ALLEGED  
03 AREA POTENTIALLY AFFECTED \_\_\_\_\_ (Acres) 04 NARRATIVE DESCRIPTION

Although ~300 yards of contaminated soil were removed, files document the potential for contaminated soils to still be present on site.

01 ☒ G DRINKING WATER CONTAMINATION ~40 02 ☐ OBSERVED (DATE \_\_\_\_\_) ☐ POTENTIAL ☐ ALLEGED  
03 POPULATION POTENTIALLY AFFECTED 04 NARRATIVE DESCRIPTION

Since March of 1986 a PRP-group (including Kaney) has been providing nearby homes w/ 18 gallons of bottled H<sub>2</sub>O per week. CERCLA SSI sample results show contamination in ground water, including residential wells.

01 ☒ H WORKER EXPOSURE/INJURY ~11 02 ☐ OBSERVED (DATE \_\_\_\_\_) ☒ POTENTIAL ☐ ALLEGED  
03 WORKERS POTENTIALLY AFFECTED 04 NARRATIVE DESCRIPTION

There is a potential for workers at Kaney to be exposed to contaminants either by soil or ground (drinking) water. None documented or observed.

01 ☐ I POPULATION EXPOSURE/INJURY 02 ☐ OBSERVED (DATE \_\_\_\_\_) ☐ POTENTIAL ☐ ALLEGED  
03 POPULATION POTENTIALLY AFFECTED 04 NARRATIVE DESCRIPTION

None documented or observed



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 3 DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE 02 SITE NUMBER

IL D064006901

II. HAZARDOUS CONDITIONS AND INCIDENTS (Continued)

01 ☒ J DAMAGE TO FLORA

02 ☐ OBSERVED (DATE \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

04 NARRATIVE DESCRIPTION

None documented or observed, however, wetlands are situated in the vicinity of Kaney + downstream

01 ☒ K DAMAGE TO FAUNA

02 ☐ OBSERVED (DATE \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

04 NARRATIVE DESCRIPTION (include number 1 of species)

In January 1990 (~date) the residential pond had fish in it. About this time an odd petroleum-like taste was noticed in the fish. Soon following, all of the fish died.

01 ☒ L CONTAMINATION OF FOOD CHAIN

02 ☐ OBSERVED (DATE \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

04 NARRATIVE DESCRIPTION

Fishing used to be done in the residential pond + was consumed. After indications of contamination, this practice was discontinued.

01 ☒ M UNSTABLE CONTAINMENT OF WASTES

02 ☐ OBSERVED (DATE \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED \_\_\_\_\_

04 NARRATIVE DESCRIPTION

Past records indicate that in the 1970s the lagoon was observed overflowing into the unnamed creek with contaminated wastes.

01 ☒ N DAMAGE TO OFFSITE PROPERTY

02 ☐ OBSERVED (DATE \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

04 NARRATIVE DESCRIPTION

Residential wells and the residential pond are no longer useable for their intended purposes due to contamination.

01 ☒ O CONTAMINATION OF SEWERS STORM DRAINS WWTPs

02 ☐ OBSERVED (DATE \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

04 NARRATIVE DESCRIPTION

In 1977 Kaney was prohibited from the Rockford Sanitary District for the disposal of effluent discharge from the on site lagoon.

01 ☐ P ILLEGAL/UNAUTHORIZED DUMPING

02 ☐ OBSERVED (DATE \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

04 NARRATIVE DESCRIPTION

None documented or observed

05 DESCRIPTION OF ANY OTHER KNOWN POTENTIAL OR ALLEGED HAZARDS

III TOTAL POPULATION POTENTIALLY AFFECTED \_\_\_\_\_

IV COMMENTS

V SOURCES OF INFORMATION (Cite specific references. e.g. SWS files, labore analysis, reports)

IEPA Bureau of Land Files  
IEPA Division of Water Files  
CERCLA Site Inspection

USGS Topographic Maps  
ISWS  
Phone Conversations



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION  
PART 4 PERMIT AND DESCRIPTIVE INFORMATION

I IDENTIFICATION

01 STATE 02 SITE NUMBER  
IL D064006901

II PERMIT INFORMATION

01 TYPE OF PERMIT ISSUED <small>(Check all that apply)</small>	02 PERMIT NUMBER	03 DATE ISSUED	04 EXPIRATION DATE	05 COMMENTS
<input type="checkbox"/> A NPDES				
<input type="checkbox"/> B UIC				
<input type="checkbox"/> C AIR				
<input type="checkbox"/> D RCRA				
<input type="checkbox"/> E RCRA INTERIM STATUS				
<input type="checkbox"/> F SPCC PLAN				
<input checked="" type="checkbox"/> G STATE <small>See IEPA Permit Sec.</small>		Nov 1981		Permit for 2 stainless steel holding tanks in lagoon area
<input type="checkbox"/> H LOCAL <small>Specify</small>				
<input type="checkbox"/> I OTHER <small>Specify</small>				
<input type="checkbox"/> NONE				

III SITE DESCRIPTION

01 STORAGE/ DISPOSAL <small>(Check all that apply)</small>	02 AMOUNT	03 UNIT OF MEASURE	04 TREATMENT <small>(Check all that apply)</small>	05 OTHER
<input checked="" type="checkbox"/> A SURFACE IMPOUNDMENT	~3000	cu yds	<input type="checkbox"/> A INCINERATION	<input checked="" type="checkbox"/> A BUILDINGS ON SITE
<input type="checkbox"/> B PILES			<input type="checkbox"/> B UNDERGROUND INJECTION	
<input type="checkbox"/> C DRUMS ABOVE GROUND			<input type="checkbox"/> C CHEMICAL/PHYSICAL	
<input checked="" type="checkbox"/> D TANK ABOVE GROUND	6,200 ~ 6,000 gallons		<input type="checkbox"/> D BIOLOGICAL	
<input type="checkbox"/> E TANK BELOW GROUND			<input type="checkbox"/> E WASTE OIL PROCESSING	
<input type="checkbox"/> F LANDFILL			<input type="checkbox"/> F SOLVENT RECOVERY	
<input type="checkbox"/> G LANDFARM			<input type="checkbox"/> G OTHER RECYCLING/RECOVERY	
<input type="checkbox"/> H OPEN DUMP			<input type="checkbox"/> H OTHER <small>(Specify)</small>	
<input type="checkbox"/> I OTHER <small>Specify</small>				06 AREA OF SITE ~5 (Acres)

07 COMMENTS

IV CONTAINMENT

01 CONTAINMENT OF WASTES <small>(Check one)</small>
<input checked="" type="checkbox"/> A ADEQUATE, SECURE <input type="checkbox"/> B MODERATE <input type="checkbox"/> C INADEQUATE POOR <input type="checkbox"/> D INSECURE UNSOUND DANGEROUS
02 DESCRIPTION OF DRUMS, DIKING LINERS, BARRIERS, ETC. The wash water from the outside of the tanks is held in the two tanks in the lagoon. The lagoon is supposed to have a liner in its base.

V ACCESSIBILITY

01 WASTE EASILY ACCESSIBLE. <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO
02 COMMENTS Unless contaminated soil

VI SOURCES OF INFORMATION (Check, specifying references, e.g. SRI, IRIS, SEMTE ANALYSIS, SOOTS)

IEPA Bureau of Land files IEPA Division of Water files CERCLA Preliminary Reconnaissance visit CERCLA SSI
--





POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 5 WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

I IDENTIFICATION

01 STATE 02 SITE NUMBER  
IL D064006901

II. DRINKING WATER SUPPLY

01 TYPE OF DRINKING SUPPLY  
(Check as applicable)

SURFACE WELL  
COMMUNITY A ☐ B ☐  
NON-COMMUNITY C ☐ D ☒

02 STATUS

ENDANGERED AFFECTED MONITORED  
A ☐ B ☐ C ☐  
D ☐ E ☒ F ☒

03 DISTANCE TO SITE

A \_\_\_\_\_ (mi)  
B. 2 1/4 (mi)

III. GROUNDWATER

01 GROUNDWATER USE IN VICINITY (Check one)

☒ A. ONLY SOURCE FOR DRINKING ☐ B. DRINKING  
(Other sources available)  
COMMERCIAL INDUSTRIAL IRRIGATION  
(No other water sources available)  
☐ C. COMMERCIAL INDUSTRIAL IRRIGATION  
(Limited other sources available)  
☐ D. NOT USED UNUSEABLE

02 POPULATION SERVED BY GROUND WATER W/ 1/2 mile ~ 70

03 DISTANCE TO NEAREST DRINKING WATER WELL on site (mi)

Depth to GROUNDWATER

~35 (ft)

05 DIRECTION OF GROUNDWATER FLOW

north east

06 DEPTH TO AQUIFER  
OF CONCERN

~35 (ft)

07 POTENTIAL YIELD  
OF AQUIFER

(gpd)

08 SOLE SOURCE AQUIFER

☒ YES ☐ NO

09 DESCRIPTION OF WELLS (including usage, depth, and location relative to population and buildings)

The wells in this area are generally put into the shallow aquifer (sands + gravels + limestone) or the deep St Peter Sandstone. However, these two may be one continuous aquifer.

10 RECHARGE AREA

☐ YES COMMENTS  
☒ NO

11 DISCHARGE AREA

☐ YES COMMENTS  
☒ NO

IV. SURFACE WATER

01 SURFACE WATER USE (Check one)

☒ A. RESERVOIR RECREATION  
DRINKING WATER SOURCE ☐ B. IRRIGATION ECONOMICALLY  
IMPORTANT RESOURCES ☐ C. COMMERCIAL INDUSTRIAL ☐ D. NOT CURRENTLY USED

02 AFFECTED/POTENTIALLY AFFECTED BODIES OF WATER

NAME

AFFECTED

DISTANCE TO SITE

Unnamed Creek

☒

~100 feet (mi)

Zander's Pond - residential

☒

~1/4 (mi)

North Fork Kent Creek

☐ ?

~1/2 (mi)

V. DEMOGRAPHIC AND PROPERTY INFORMATION

01 TOTAL POPULATION WITHIN

ONE (1) MILE OF SITE

A ~130  
NO. OF PERSONS

TWO (2) MILES OF SITE

B ~3,650  
NO. OF PERSONS

THREE (3) MILES OF SITE

C ~13,550  
NO. OF PERSONS

02 DISTANCE TO NEAREST POPULATION

~40 feet (mi)

03 NUMBER OF BUILDINGS WITHIN TWO (2) MILES OF SITE

>500

04 DISTANCE TO NEAREST OFF-SITE BUILDING

~40 feet (mi)

05 POPULATION WITHIN VICINITY OF SITE (Provide narrative description of nature of population within vicinity of site, e.g. rural, village, densely populated urban area)

The population in the vicinity of Kaney is made up of workers in neighboring industries (including Kaney) + residen



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 5 WATER DEMOGRAPHIC AND ENVIRONMENTAL DATA

I IDENTIFICATION

01 STATE 02 SITE NUMBER  
IL D064006901

VI ENVIRONMENTAL INFORMATION

01 PERMEABILITY OF UNSATURATED ZONE (Check one)

☐ A  $10^{-6}$  -  $10^{-8}$  cm/sec ☒ B  $10^{-7}$  -  $10^{-6}$  cm/sec ☐ C  $10^{-7}$  -  $10^{-3}$  cm/sec ☐ D GREATER THAN  $10^{-3}$  cm/sec

02 PERMEABILITY OF BEDROCK (Check one)

☐ A IMPERMEABLE (Less than  $10^{-6}$  cm/sec) ☒ B RELATIVELY IMPERMEABLE ( $10^{-4}$  -  $10^{-6}$  cm/sec) ☐ C RELATIVELY PERMEABLE ( $10^{-2}$  -  $10^{-1}$  cm/sec) ☐ D VERY PERMEABLE (Greater than  $10^{-2}$  cm/sec)

03 DEPTH TO BEDROCK

~30 (ft)

04 DEPTH OF CONTAMINATED SOIL ZONE

estimated 14 (ft)

05 SOIL pH

unknown

06 NET PRECIPITATION

~2 (in)

07 ONE YEAR 24 HOUR RAINFALL

25 (in)

08 SLOPE

SITE SLOPE  
25 %

DIRECTION OF SITE SLOPE  
South

TERRAIN AVERAGE SLOPE  
67 %

09 FLOOD POTENTIAL

out of 500 year  
SITE IS IN YEAR FLOODPLAIN

10

☐ SITE IS ON BARRIER ISLAND COASTAL HIGH HAZARD AREA RIVERINE FLOODWAY

11 DISTANCE TO WETLANDS 5 acre minimum

ESTUARINE

A NA (mi)

OTHER

B ~120 feet (mi)

12 DISTANCE TO CRITICAL HABITAT (of endangered species)

No known endangered species (mi)  
ENDANGERED SPECIES

13 LAND USE IN VICINITY

DISTANCE TO

COMMERCIAL/INDUSTRIAL

A 0 (mi)


RESIDENTIAL AREAS NATIONAL/STATE PARKS  
FORESTS OR WILDLIFE RESERVES

B ~40 feet (mi)

AGRICULTURAL LANDS  
PRIME AG LAND AG LAND

C ~200 feet (mi) D (mi)

14 DESCRIPTION OF SITE IN RELATION TO SURROUNDING TOPOGRAPHY



VII SOURCES OF INFORMATION (Cite specific references. E.g., State 1994, Sample analysis, reports)

IEPA Bureau of Land Files  
USGS Topographic Map  
Flood Insurance Rate Map

Illinois Department of Conservation  
SCS Wetland Maps



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 8 SAMPLE AND FIELD INFORMATION

I IDENTIFICATION

01 STATE 02 SITE NUMBER

II SAMPLES TAKEN

SAMPLE TYPE	01 NUMBER OF SAMPLES TAKEN	02 SAMPLES SENT TO	03 ESTIMATED DATE RESULTS AVAILABLE
GROUNDWATER	6	ARDL Laboratory, Mt Vernon, IL	May 1992
SURFACE WATER			
WASTE			
AIR			
RUNOFF			
SPILL			
SOIL / Sediment	9	ARDL Laboratory, Mt Vernon, IL	May 1992
VEGETATION			
OTHER			

III FIELD MEASUREMENTS TAKEN

01 TYPE	02 COMMENTS
(HNU) Photoionization Detector	Sample G102 read 300 units over background

IV PHOTOGRAPHS AND MAPS

01 TYPE <input checked="" type="checkbox"/> GROUND <input checked="" type="checkbox"/> AERIAL	02 IN CUSTODY OF <u>Illinois EPA</u> <small>Name of organization or individual</small>
03 MAPS <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO	04 LOCATION OF MAPS <u>IEPA Springfield, IL</u>

V OTHER FIELD DATA COLLECTED (Provide narrative description)

See CERCLA SSI Report

VI SOURCES OF INFORMATION (Cite specific references. e.g. SSI files, sample analysis, reports)

CERCLA Screening Site Inspection



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 7 OWNER INFORMATION

I IDENTIFICATION

01 STATE 02 SITE NUMBER  
IL D064006901

II CURRENT OWNER(S)				PARENT COMPANY (If applicable)			
01 NAME Bell Leasing Company		02 D+B NUMBER		08 NAME		09 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD, etc.) 1515 S. Meridian		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD, etc.)		11 SIC CODE	
05 CITY Rockford		06 STATE IL	07 ZIP CODE 61102	12 CITY		13 STATE	14 ZIP CODE
01 NAME		02 D+B NUMBER		08 NAME		09 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD, etc.)		11 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	12 CITY		13 STATE	14 ZIP CODE
01 NAME		02 D+B NUMBER		08 NAME		09 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD, etc.)		11 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	12 CITY		13 STATE	14 ZIP CODE
01 NAME		02 D+B NUMBER		08 NAME		09 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD, etc.)		11 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	12 CITY		13 STATE	14 ZIP CODE
III PREVIOUS OWNER(S) (List most recent first)				IV REALTY OWNER(S) (If applicable, list most recent first)			
01 NAME Ed Kanev		02 D+B NUMBER		01 NAME		02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD, etc.) 7222 Cunningham		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE	
05 CITY Rockford		06 STATE IL	07 ZIP CODE 61102	05 CITY		06 STATE	07 ZIP CODE
01 NAME		02 D+B NUMBER		01 NAME		02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	05 CITY		06 STATE	07 ZIP CODE
01 NAME		02 D+B NUMBER		01 NAME		02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	05 CITY		06 STATE	07 ZIP CODE
V SOURCES OF INFORMATION (Check specific reference, e.g., SRI, HRA, SRI, etc.)							



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 8 OPERATOR INFORMATION

I IDENTIFICATION

01 STATE 02 SITE NUMBER  
IL D064006901

II CURRENT OPERATOR (Provide if different from owner)				OPERATOR'S PARENT COMPANY (if applicable)			
01 NAME Richard Bell		02 D+8 NUMBER		10 NAME		11 D+8 NUMBER	
03 STREET ADDRESS (P.O. Box, RFD # etc.) 1515 S Meridian		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD # etc.)		13 SIC CODE	
05 CITY Rockford		06 STATE IL	07 ZIP CODE 61102	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION Total ~20		09 NAME OF OWNER Bell Leasing Company					
III PREVIOUS OPERATOR(S) (List most recent first, provide only if different from owner)				PREVIOUS OPERATORS' PARENT COMPANIES (if applicable)			
01 NAME Ron Bell		02 D+8 NUMBER		10 NAME		11 D+8 NUMBER	
03 STREET ADDRESS (P.O. Box, RFD # etc.) 1515 S. Meridian		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD # etc.)		13 SIC CODE	
05 CITY Rockford		06 STATE IL	07 ZIP CODE 61102	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD Bell Leasing Company					
01 NAME		02 D+8 NUMBER		10 NAME		11 D+8 NUMBER	
03 STREET ADDRESS (P.O. Box, RFD # etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD # etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					
01 NAME		02 D+8 NUMBER		10 NAME		11 D+8 NUMBER	
03 STREET ADDRESS (P.O. Box, RFD # etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD # etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					
01 NAME		02 D+8 NUMBER		10 NAME		11 D+8 NUMBER	
03 STREET ADDRESS (P.O. Box, RFD # etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD # etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					
IV SOURCES OF INFORMATION (Cite specific references, e.g. state files, sample analysis, reports)							



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 9 - GENERATOR/TRANSPORTER INFORMATION

I IDENTIFICATION	
01 STATE	02 SITE NUMBER
IL	D064006901

II ON-SITE GENERATOR

01 NAME Kaney Transportation, Inc.	02 D+B NUMBER	Kaney is a small quantity generator	
03 STREET ADDRESS (P O Box, RFD, etc.) 7222 Cunningham Rd	04 SIC CODE		
05 CITY Rockford	06 STATE IL		07 ZIP CODE 61102

III OFF SITE GENERATOR(S)

01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER		
03 STREET ADDRESS (P O Box, RFD, etc.)	04 SIC CODE	03 STREET ADDRESS (P O Box, RFD, etc.)	04 SIC CODE		
05 CITY	06 STATE	07 ZIP CODE	05 CITY	06 STATE	07 ZIP CODE
01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER		
03 STREET ADDRESS (P O Box, RFD, etc.)	04 SIC CODE	03 STREET ADDRESS (P O Box, RFD, etc.)	04 SIC CODE		
05 CITY	06 STATE	07 ZIP CODE	05 CITY	06 STATE	07 ZIP CODE

IV TRANSPORTER(S)

01 NAME Kaney Transportation, Inc.	02 D+B NUMBER	01 NAME	02 D+B NUMBER		
03 STREET ADDRESS (P O Box, RFD, etc.) 7222 Cunningham Rd	04 SIC CODE	03 STREET ADDRESS (P O Box, RFD, etc.)	04 SIC CODE		
05 CITY Rockford	06 STATE IL	07 ZIP CODE 61102	05 CITY	06 STATE	07 ZIP CODE
01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER		
03 STREET ADDRESS (P O Box, RFD, etc.)	04 SIC CODE	03 STREET ADDRESS (P O Box, RFD, etc.)	04 SIC CODE		
05 CITY	06 STATE	07 ZIP CODE	05 CITY	06 STATE	07 ZIP CODE

V SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

IEPA Bureau of Land Files



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 10 PAST RESPONSE ACTIVITIES

I. IDENTIFICATION

01 STATE IL 02 SITE NUMBER DO64006901

II PAST RESPONSE ACTIVITIES

01 <input checked="" type="checkbox"/> A WATER SUPPLY CLOSED 04 DESCRIPTION <u>Several private residential + industrial wells in the area have been closed due to contamination</u>	02 DATE <u>1986</u>	03 AGENCY _____
01 <input checked="" type="checkbox"/> B TEMPORARY WATER SUPPLY PROVIDED 04 DESCRIPTION <u>18 gallons every two weeks have been provided to proximal residents by PRP-group</u>	02 DATE _____	03 AGENCY _____
01 <input checked="" type="checkbox"/> C PERMANENT WATER SUPPLY PROVIDED 04 DESCRIPTION <u>Some new wells have been installed to replace contaminated wells (Not all new wells can be used)</u>	02 DATE _____	03 AGENCY _____
01 <input checked="" type="checkbox"/> D SPILLED MATERIAL REMOVED 04 DESCRIPTION <u>The materials in the lagoon + in area of buried drums has been removed</u>	02 DATE _____	03 AGENCY _____
01 <input checked="" type="checkbox"/> E CONTAMINATED SOIL REMOVED 04 DESCRIPTION <u>~300 yards of contaminated soils were removed</u>	02 DATE <u>1989</u>	03 AGENCY _____
01 <input type="checkbox"/> F WASTE REPACKAGED 04 DESCRIPTION <u>NA</u>	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> G WASTE DISPOSED ELSEWHERE 04 DESCRIPTION <u>NA</u>	02 DATE _____	03 AGENCY _____
01 <input checked="" type="checkbox"/> H ON SITE BURIAL 04 DESCRIPTION <u>Drums + tanks were excavated the summer of 1989</u>	02 DATE <u>1989</u>	03 AGENCY _____
01 <input type="checkbox"/> I IN SITU CHEMICAL TREATMENT 04 DESCRIPTION <u>NA</u>	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> J IN SITU BIOLOGICAL TREATMENT 04 DESCRIPTION <u>NA</u>	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> K IN SITU PHYSICAL TREATMENT 04 DESCRIPTION <u>NA</u>	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> L ENCAPSULATION 04 DESCRIPTION <u>NA</u>	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> M EMERGENCY WASTE TREATMENT 04 DESCRIPTION <u>NA</u>	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> N CUTOFF WALLS 04 DESCRIPTION <u>NA</u>	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> O EMERGENCY DIKING/SURFACE WATER DIVERSION 04 DESCRIPTION <u>NA</u>	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> P CUTOFF TRENCHES/SUMP 04 DESCRIPTION <u>NA</u>	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> Q SUBSURFACE CUTOFF WALL 04 DESCRIPTION <u>NA</u>	02 DATE _____	03 AGENCY _____



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 10 PAST RESPONSE ACTIVITIES

I. IDENTIFICATION

01 STATE 02 SITE NUMBER  
IL D064006901

II. PAST RESPONSE ACTIVITIES (Continued)

01 ☐ R BARRIER WALLS CONSTRUCTED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

NA

01 ☐ S CAPPING/COVERING

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

04 DESCRIPTION In December 1980 the IEPA verified that Kamy had Complied w/ instructions to install a clay base of no less than one foot deep for the lagoon floor w/ an imperv-

01 ☐ T BULK TANKAGE REPAIRED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

NA

epac industrial liner over it

01 ☐ U GROUT CURTAIN CONSTRUCTED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

NA

01 ☐ V BOTTOM SEALED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

NA

01 ☐ W GAS CONTROL  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

NA

01 ☐ X FIRE CONTROL  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

NA

01 ☐ Y LEACHATE TREATMENT  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

NA

01 ☐ Z AREA EVACUATED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

NA

01 ☐ 1 ACCESS TO SITE RESTRICTED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

NA

01 ☐ 2 POPULATION RELOCATED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

NA

01 ☐ 3 OTHER REMEDIAL ACTIVITIES  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

None

III. SOURCES OF INFORMATION (Cite specific references, e.g. State files, sample analysis, reports)

IEPA Bureau of Landfiles





POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 11 ENFORCEMENT INFORMATION

I IDENTIFICATION

01 STATE 02 SITE NUMBER  
IL' D064006901

II. ENFORCEMENT INFORMATION

01 PAST REGULATORY/ENFORCEMENT ACTION ☒ YES ☐ NO

02 DESCRIPTION OF FEDERAL, STATE, LOCAL REGULATORY/ENFORCEMENT ACTION

The IEPA instructed Kaney to remove & properly dispose of all contaminated solid wastes, liquid wastes & sludges from the lagoon. Kaney also had to install a clay base of no less than one foot deep for the lagoon floor & an impermeable industrial liner to cover the clay base. The IEPA verified these settlement conditions on December 12, 1980.

III SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

IEPA Files

## APPENDIX C

### TARGET COMPOUND LIST

## TARGET COMPOUND LIST

### Volatile Target Compounds

Chloromethane	1,2-Dichloropropane
Bromomethane	cis-1,3-Dichloropropene
Vinyl Chloride	Trichloroethene
Chloroethane	Dibromochloromethane
Methylene Chloride	1,1,2-Trichloroethane
Acetone	Benzene
Carbon Disulfide	trans-1,3-Dichloropropene
1,1-Dichloroethene	Bromoform
1,1-Dichloroethane	4-Methyl-2-pentanone
1,2-Dichloroethene (total)	2-Hexanone
Chloroform	Tetrachloroethene
1,2-Dichloroethane	1,1,2,2-Tetrachloroethane
2-Butanone	Toluene
1,1,1-Trichloroethane	Chlorobenzene
Carbon Tetrachloride	Ethylbenzene
Vinyl Acetate	Styrene
Bromodichloromethane	Xylenes (total)

### Base/Neutral Target Compounds

Hexachloroethane	2,4-Dinitrotoluene
bis(2-Chloroethyl) Ether	Diethylphthalate
Benzyl Alcohol	N-Nitrosodiphenylamine
bis(2-Chloroisopropyl) Ether	Hexachlorobenzene
N-Nitroso-Di-n-Propylamine	Phenanthrene
Nitrobenzene	4-Bromophenyl-phenylether
Hexachlorobutadiene	Anthracene
2-Methylnaphthalene	Di-n-Butylphthalate
1,2,4-Trichlorobenzene	Fluoranthene
Isophorone	Pyrene
Naphthalene	Butylbenzylphthalate
4-Chloroaniline	bis(2-Ethylhexyl) Phthalate
bis(2-chloroethoxy) Methane	Chrysene
Hexachlorocyclopentadiene	Benzo(a) Anthracene
2-Chloronaphthalene	3,3'-Dichlorobenzidene
2-Nitroaniline	Di-n-Octyl Phthalate
Acenaphthylene	Benzo(b) Fluoranthene
3-Nitroaniline	Benzo(k) Fluoranthene
Acenaphthene	Benzo(a) Pyrene
Dibenzofuran	Indeno(1,2,3-cd) Pyrene
Dimethyl Phthalate	Dibenz(a,h) Anthracene
2,6-Dinitrotoluene	Benzo(g,h,i) Perylene
Fluorene	1,2-Dichlorobenzene
4-Nitroaniline	1,3-Dichlorobenzene
4-Chlorophenyl-phenylether	1,4-Dichlorobenzene

### Acid Target Compounds

Benzoic Acid	2,4,6-Trichlorophenol
Phenol	2,4,5-Trichlorophenol
2-Chlorophenol	4-Chloro-3-methylphenol
2-Nitrophenol	2,4-Dinitrophenol
2-Methylphenol	2-Methyl-4,6-dinitrophenol
2,4-Dimethylphenol	Pentachlorophenol
4-Methylphenol	4-Nitrophenol
2,4-Dichlorophenol	

### Pesticide/PCB Target Compounds

alpha-BHC	Endrin Ketone
beta-BHC	Endosulfan Sulfate
delta-BHC	Methoxychlor
gamma-BHC (Lindane)	alpha-Chlorodane
Heptachlor	gamma-Chlorodane
Aldrin	Toxaphene
Heptachlor epoxide	Aroclor-1016
Endosulfan I	Aroclor-1221
4,4'-DDE	Aroclor-1232
Dieldrin	Aroclor-1242
Endrin	Aroclor-1248
4,4'-DDD	Aroclor-1254
Endosulfan II	Aroclor-1260
4,4'-DDT	

### Inorganic Target Compounds

Aluminum	Manganese
Antimony	Mercury
Arsenic	Nickel
Barium	Potassium
Beryllium	Selenium
Cadmium	Silver
Calcium	Sodium
Chromium	Thallium
Cobalt	Vanadium
Copper	Zinc
Iron	Cyanide
Lead	Sulfide
Magnesium	Sulfate

## **APPENDIX D**

### **IEPA SITE PHOTOGRAPHS**



# INSPECTION PHOTOS

DATE: <u>11 / 6 / 91</u>	SITE #: <u>201030007</u> CO.: <u>Winnebago</u>
TIME: <u>~ 11:55A</u>	SITE NAME: <u>Kaney Transportation, Inc.</u>
PHOTOGRAPH TAKEN BY: <u>Ken Corkill</u>	
COMMENTS: Pictures taken toward: <u>the north from northeast corner of Kaney Sample G109</u>	
PHOTO #: <u>1</u>	




DATE: <u>11 / 6 / 91</u>
TIME: <u>~ 11:55A</u>
PHOTOGRAPH TAKEN BY: <u>Ken Corkill</u>
COMMENTS: Pictures taken toward: <u>Southwest from northeast corner of Kaney Sample G109</u>
PHOTO #: <u>2</u>







## INSPECTION PHOTOS

DATE: 11/6/92	SITE #: 201030001 + CO.: Winnebago
TIME: ~1:05 PM	SITE NAME: Kaney Transportation, Inc.
PHOTOGRAPH TAKEN BY: Ken Corkill	
COMMENTS: Pictures taken toward: north along east property line of Kaney	
Sample G 101	
PHOTO #: 3	


DATE: 11/6/92
TIME: ~1:05 PM
PHOTOGRAPH TAKEN BY: Ken Corkill
COMMENTS: Pictures taken toward: west along east property line of Kaney
Sample G 101
PHOTO #: 4








## INSPECTION PHOTOS

DATE: 11/16/91	SITE #: 201030001 + CO.: Winnebago
TIME: ~3:15P	SITE NAME: Kaneu Transportation, Inc.
PHOTOGRAPH TAKEN BY: Kim Nika	
COMMENTS: Pictures taken toward: West Southwest	
toward Marathon	
Oil on northwest corner of property	
5 monitoring wells were observed in NE corner of Marathon	
PHOTO #: 5	

DATE: 11/16/91
TIME: ~3:45P
PHOTOGRAPH TAKEN BY: Sheila Murphy
COMMENTS: Pictures taken toward: east north east
On northwest corner of Kaneu
picture of well contents bailed for G102-
product floating on top
PHOTO #: 6







## INSPECTION PHOTOS

DATE: 11/16/91	SITE #: 201030007 + CO.: Winnebago
TIME: ~3:45P	SITE NAME: Kaney Transportation, Inc.
PHOTOGRAPH TAKEN BY: Sheila Murphy	
COMMENTS: Pictures taken toward: west toward Marathon Oil on northwest corner of Kaney property picture of well contents bailed for G102 product floating on top PHOTO #: 7	




DATE: 11/16/91
TIME: ~3:45P
PHOTOGRAPH TAKEN BY: Sheila Murphy
COMMENTS: Pictures taken toward: west toward Marathon Oil on northwest corner of Kaney property picture of well contents bailed for G102 PHOTO #: 8







# INSPECTION PHOTOS

DATE: 11/6/91	SITE #: 201030001 + CO.: Winnebago
TIME: ~4:15 P	SITE NAME: Kaney Transportation, Inc.
PHOTOGRAPH TAKEN BY: Sheila Murphy	
COMMENTS: Pictures taken toward: east northeast on northwest corner of Kaney property	
Sample G102	
PHOTO #: 9	

DATE: 11/6/91
TIME: ~4:15 P
PHOTOGRAPH TAKEN BY: Sheila Murphy
COMMENTS: Pictures taken toward: west southwest on northwest corner of Kaney property
Sample G102
PHOTO #: 10







# INSPECTION PHOTOS

DATE: 11/14/91	SITE #: 201030001 + CO.: Winnebago
TIME: ~5:35 P	SITE NAME: Kaney Transportation, Inc.
PHOTOGRAPH TAKEN BY: Sheila Murphy	
COMMENTS: Pictures taken toward: faucet in Abels' home	
Sample G202	
PHOTO #: 11	




DATE: 11/14/91
TIME: ~5:35 P
PHOTOGRAPH TAKEN BY: Sheila Murphy
COMMENTS: Pictures taken toward: faucet in Abels' home
Sample G202
PHOTO #: 12







## INSPECTION PHOTOS

DATE: 11/7/91	SITE #: 201030001 + CO.: Winnebago
TIME: ~8:35A	SITE NAME: Kaney Transportation, Inc.
PHOTOGRAPH TAKEN BY: Kim Nika	
COMMENTS: Pictures taken toward: South at east end of residential pond	
Sample X108	
PHOTO #: 13	

DATE: 11/7/91
TIME: ~8:35 A
PHOTOGRAPH TAKEN BY: Kim Nika
COMMENTS: Pictures taken toward: South southwest at east end of residential pond
Sample X108
PHOTO #: 14







# INSPECTION PHOTOS

DATE: 11/7/91	SITE #: 201030001 + CO.: Winnebago
TIME: ~8:40A	SITE NAME: Kaneu Transportation, Inc.

PHOTOGRAPH TAKEN


BY: Kim Nika

COMMENTS: Pictures taken  
toward: east at east

end of residential  
pond

Sample X108

PHOTO #: 15



DATE: 11/7/91

TIME: 8:55A

PHOTOGRAPH TAKEN

BY: Kim Nika

COMMENTS: Pictures taken  
toward: south at

west end of residential  
pond

Sample X109

PHOTO #: 16

SITE KANEU TRANSPORT  
DATE 11-7-91  
SAMPLE X108



SITE KANEU TRANSPORT  
DATE 11-7-91 TIME 8:50 AM  
SAMPLE X109






## INSPECTION PHOTOS

DATE: 11/7/91	SITE #: 201030001 + CO.: Winnebago
TIME: 8:55A	SITE NAME: Kaneu Transportation, Inc.
PHOTOGRAPH TAKEN BY: Kim Nika	
COMMENTS: Pictures taken toward: West at west end of residential pond	
Sample X109	
PHOTO #: 17	

DATE: 11/7/91
TIME: 9:10A
PHOTOGRAPH TAKEN BY: Kim Nika
COMMENTS: Pictures taken toward: West at south west corner of Cunningham Rd + Meridian Rd. intersection
Sample X107
PHOTO #: 18







# INSPECTION PHOTOS

DATE: 11/7/91	SITE #: 201030001 + CO.: Winnebago
TIME: 9:10A	SITE NAME: Kaneu Transportation, Inc.

PHOTOGRAPH TAKEN

BY: Kim Nika

COMMENTS: Pictures taken  
toward: north at

southwest corner of  
Cunningham Rd. +  
Meridian Rd  
intersection  
Sample X107

PHOTO #: 19



DATE: 11/7/91

TIME: 10:00 A


PHOTOGRAPH TAKEN

BY: Kim Nika

COMMENTS: Pictures taken  
toward: north 22' 11"

South of southern boundary  
fence of pit + 75' 9" east  
of site east boundary  
fence  
Sample X106

PHOTO #: 20







# INSPECTION PHOTOS

DATE: 11/7/91	SITE #: 201030001 + CO.: Winnebago
TIME: ~10:00A	SITE NAME: Kanev Transportation, Inc.
PHOTOGRAPH TAKEN BY: Kim Nika	
COMMENTS: Pictures taken toward: South 22'11"	
South of Southern boundary fence of pit +75'9" east of site east boundary fence	
Sample X106	
PHOTO #: 21	



DATE: 11/7/91
TIME: 10:05A
PHOTOGRAPH TAKEN BY: Kim Nika
COMMENTS: Pictures taken toward: tank along unnamed creek where runoff was observed
PHOTO #: 22







# INSPECTION PHOTOS

DATE: 11/7/91	SITE #: 201030001 + CO.: Winnebago
TIME: ~10:05A	SITE NAME: Kaney Transportation, Inc.
PHOTOGRAPH TAKEN BY: Kim Nika	
COMMENTS: Pictures taken toward: bank of unnamed creek, where runoff was observed.	
PHOTO #: 23	



DATE: 11/7/91
TIME: ~10:25A
PHOTOGRAPH TAKEN BY: Kim Nika
COMMENTS: Pictures taken toward: east southeast along unnamed creek Sample X105
PHOTO #: 24







# INSPECTION PHOTOS

DATE: 11/7/91	SITE #: 201030001 + CO.: Winnebago
TIME: ~10:25A	SITE NAME: Kaney Transportation, Inc.

PHOTOGRAPH TAKEN

BY:

Kim Nika

COMMENTS: Pictures taken

toward:

east southeast

along unnamed

creek

Sample: X105

PHOTO #:

25



DATE: 11/7/91

TIME: ~10:25A

PHOTOGRAPH TAKEN

BY:

Kim Nika

COMMENTS: Pictures taken

toward:


east along

unnamed creek

Sample X105

PHOTO #:


26








# INSPECTION PHOTOS

DATE: 11/7/91	SITE #: 201030001 + CO.: Winnebago
TIME: ~10:35A	SITE NAME: Kaneu Transportation, Inc.
PHOTOGRAPH TAKEN BY: Kim Nika	
COMMENTS: Pictures taken toward: west toward Marathon Oil	
Note: low center is a pipe in the hill	
PHOTO #: 27	

DATE: 11/7/91
TIME: ~10:35A
PHOTOGRAPH TAKEN BY: Kim Nika
COMMENTS: Pictures taken toward: west toward Marathon Oil
Note: in center is a pipe in the hill
PHOTO #: 28







# INSPECTION PHOTOS

DATE: 11/7/91	SITE #: 201030001 + CO.: Winnebago
TIME: 10:45A	SITE NAME: Kaney Transportation, Inc.

PHOTOGRAPH TAKEN


BY: Kim Nika

COMMENTS: Pictures taken

toward: West towards

Marathon Oil  
along west side  
of Kaney  
property  
Sample X101

PHOTO #: 29



DATE: 11/7/91

TIME: 10:45A

PHOTOGRAPH TAKEN

BY: Kim Nika

COMMENTS: Pictures taken

toward: north north

east along west  
side of Kaney  
property  
Sample X101


PHOTO #: 30








# INSPECTION PHOTOS

DATE: 11/7/91	SITE #: 201030001 + CO.: Winnebago
TIME: 11:10 A	SITE NAME: Kaney Transportation, Inc.
PHOTOGRAPH TAKEN BY: Sheila Murphy	
COMMENTS: Pictures taken toward: east, in lagoon	
Sample X104	
PHOTO #: 31	

DATE: 11/7/91
TIME: 11:10 A
PHOTOGRAPH TAKEN BY: Sheila Murphy
COMMENTS: Pictures taken toward: east in lagoon
Sample X104
PHOTO #: 32







# INSPECTION PHOTOS

DATE: 11/7/91	SITE #: 201030001 + CO.: Winnebago
TIME: ~11:20A	SITE NAME: Kaney Transportation, Inc.

PHOTOGRAPH TAKEN

BY: Sheila Murphy

COMMENTS: Pictures taken  
toward: west along

west side of  
Kaney property  
Sample G104

PHOTO #: 33



DATE: 11/7/91

TIME: ~11:20A

PHOTOGRAPH TAKEN

BY: Sheila Murphy

COMMENTS: Pictures taken  
toward: northeast

along west side of  
Kaney property  
Sample: G104

PHOTO #: 34







# INSPECTION PHOTOS

DATE: 11/7/91	SITE #: 201030001 + CO.: Winnebago
TIME: ~11:55A	SITE NAME: Kaneu Transportation, Inc.

PHOTOGRAPH TAKEN

BY: Kim Nika

COMMENTS: Pictures taken

toward: west

along Deets' west side of backyard  
Sample X102

PHOTO #: 35



SITE 201030001  
DATE 11-7-91 TIME 11:50  
SAMPLE X102



DATE: 11/7/91

TIME: ~11:55A

PHOTOGRAPH TAKEN

BY: Kim Nika

COMMENTS: Pictures taken

toward: northeast

along Deets' west side of backyard  
Sample X102

PHOTO #: 36





# INSPECTION PHOTOS


DATE: 11/7/91	SITE #: 201030001 + CO.: Winnebago
TIME: ~1:25 P	SITE NAME: Kaney Transportation, Inc.

PHOTOGRAPH TAKEN  
BY: Kim Nika

COMMENTS: Pictures taken  
toward: north on

South side of  
Falconer home  
Sample: G203

PHOTO #: 37



DATE: 11/7/91

TIME: ~1:40 P


PHOTOGRAPH TAKEN

BY: Sheila Murphy

COMMENTS: Pictures taken  
toward: east along


east side of South  
Weldon - can see  
Marathon Oil in  
background  
Sample: X103


PHOTO #: 38





## INSPECTION PHOTOS

DATE: 11/7/91	SITE #: 201030007 + CO.: Winnebago
TIME: ~1:40 P	SITE NAME: Kaney Transportation, Inc.
PHOTOGRAPH TAKEN BY: Sheila Murphy	
COMMENTS: Pictures taken toward: north northwest	
along east side of South Weldon	
PHOTO #: 39	SITE KANEY TRANSPORT DATE 11-7-91 TIME 1:35 PM SAMPLE X103

[illegible]

**APPENDIX E**

**WELL LOGS**

White Copy -  
Ill. Dept. of Public Health  
Yellow Copy - Well Contractor  
Blue Copy - Well Owner

# INSTRUCTIONS TO DRILLERS

FILL IN ALL PERTINENT INFORMATION REQUESTED AND MAIL ORIGINAL TO STATE  
DEPARTMENT OF PUBLIC HEALTH CONSUMER HEALTH PROTECTION 535 WEST  
JEFFERSON SPRINGFIELD ILLINOIS 62761 DO NOT DETACH GEOLOGICAL/WATER  
SURVEYS SECTION BE SURE TO PROVIDE PROPER WELL LOCATION.

## ILLINOIS DEPARTMENT OF PUBLIC HEALTH WELL CONSTRUCTION REPORT

### 1 Type of Well

- a Dug ☐ Bored ☐ Hole Diam 5 in Depth 265 ft  
Curb material ☐ Buried Slab Yes ☐ No ☐  
b Driven ☐ Drive Pipe Diam ☐ in Depth ☐ ft  
c Drilled ☒ Finished in Drift ☐ In Rock ☒  
Tubular ☐ Gravel Packed ☐  
d Grout

(KIND)	FROM (Ft)	TO (Ft)

### 2 Distance to Nearest

- Building 125 Ft. Seepage Tile Field 100  
Cess Pool ☐ Sewer (non Cast iron) ☐  
Privy ☐ Sewer (Cast iron) ☐  
Septic Tank 75 Barnyard ☐  
Leaching Pit ☐ Manure Pile ☐

### 3 Well furnishes water for human consumption? Yes ☒ No ☐

### 4 Date well completed 1-24-86

### 5 Permanent Pump Installed? Yes ☐ Date ☐ No ☐

Manufacturer RED JACKET Type ☐ Location ☐  
Capacity ☐ gpm Depth of Setting ☐ Ft

### 6 Well Top Sealed? Yes ☒ No ☐ Type LP-5

### 7 Pitless Adapter Installed? Yes ☒ No ☐

Manufacturer MARTIN Model Number BP-10  
How attached to casing? BOLTED

### 8 Well Disinfected? Yes ☒ No ☐

### 9 Pump and Equipment Disinfected? Yes ☒ No ☐


### 10 Pressure Tank Size ☐ gal Type ☐ Location ☐

### 11. Water Sample Submitted? Yes ☐ No ☐

#### REMARKS

Winn - No - 4920

P. # - 5922



IDPH 4 065  
1/74 - KNB 1

## GEOLOGICAL AND WATER SURVEYS WELL RECORD

### 10 Proper

Address **non-responsive**  
Driller JESSIE DEAMAN License No 92-599

### 11 Permit No 121147 Date 10-25-85


### 12 Water from SANDSTONE 13 County WINNEBAGO

at depth 245 to 265 ft Sec 12.70

### 14 Screen Diam ☐ in Twp 26N

Length ☐ ft Slot ☐ Rge 11E

Elev ☐



### 15 Casing and Liner Pipe

Diam. (in)	Kind and Weight	From (Ft)	To (Ft)

SHOW  
LOCATION IN  
SECTION PLAT  
SE NW SW

### 16 Size Hole below casing ☐ in

### 17 Static level ☐ ft below casing top which is ☐ ft above ground level Pumping level ☐ ft when pumping at ☐ gpm for ☐ hours

18 FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
<u>CLAY</u>	<u>35</u>	<u>35</u>
<u>SAND</u>	<u>5</u>	<u>40</u>
<u>LIMESTONE</u>	<u>205</u>	<u>245</u>
<u>SAND STONE</u>	<u>20</u>	<u>265</u>

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED Jessie Deaman DATE ☐

White Copy -  
Ill Dept of Public Health  
Yellow Copy - Well Contractor  
Blue Copy - Well Owner

FILL IN ALL PERTINENT INFORMATION REQUESTED AND MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH, ROOM 6 STATE OFFICE BUILDING SPRINGFIELD ILLINOIS 62706 DO NOT DETACH GEOLOGICAL/WATER SURVEYS SECTION BE SURE TO PROVIDE PROPER WELL LOCATION

## ILLINOIS DEPARTMENT OF PUBLIC HEALTH WELL CONSTRUCTION REPORT

### 1 Type of Well

- a Dug ☐ Bored ☐ Hole Diam  in Depth  ft  
Curb material  Buried Slab Yes ☐ No ☐  
b Driven ☐ Drive Pipe Diam  in Depth  ft  
c Drilled ☒ Finished in Drift ☐ In Rock ☒  
Tubular ☐ Gravel Packed ☐  
d Grout

(KIND)	FROM (FT)	TO (FT)
CLAY	0	20

### 2 Distance to Nearest

Building 34 Ft Seepage Tile Field 100  
Cess Pool  Sewer (non Cast iron)   
Privy  Sewer (Cast iron)   
Septic Tank 25 Barnyard   
Leaching Pit  Manure Pile

### 3 Is water from this well to be used for human consumption?

Yes ☒ No ☐

### 4 Date well completed 11-14-75

### 5 Permanent Pump Installed? Yes ☒ No ☐

Manufacturer RED JACKET Type 3.5 BARCL  
Capacity 10 gpm Depth of setting 63 ft

### 6 Well Top Sealed? Yes ☒ No ☐

### 7 Pitless Adaptor Installed? Yes ☒ No ☐

### 8 Well Disinfected? Yes ☒ No ☐

### 9 Water Sample Submitted? Yes ☒ No ☐

REMARKS

IDPM 4 0/5  
10/68

## GEOLOGICAL AND WATER SURVEYS WELL RECORD

### 10 Property

Address

non-responsive

Driller GERALD ROSENBLUM License No 92314

11 Permit No 40766 Date 9-4-75

12 Water from LIMESTONE 13 County WINNEGAGO

Formation  
at depth 31 to 50 ft Sec 2350

14 Screen Diam  in Twp 26N

Length  ft Slot  Rge 11E

Elev


### 15 Casing and Liner Pipe

Diam (in)	Kind and Weight	From (Ft)	To (Ft)
6	BLK. A53B 11.45LB	1	34

SHOW  
LOCATION IN  
SECTION PLAT  
SE N E N W

- 16 Size Hole below casing 6 in  
17 Static level 11 ft below casing top which is 1 ft  
above ground level Pumping level 17 ft when pumping at 11  
gpm for 3 hours

18 FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
CLAY	31	31
LIMESTONE	49	80
WILKINITE	40	120

(CONTINUED ON SEPARATE SHEET IF NECESSARY)

SIGNED David T. Rosenberg DATE 11-20-75

White Copy -  
Ill Dept of Public Health  
Yellow Copy - Well Contractor  
Blue Copy - Well Owner

# INSTRUCTIONS TO DRILLERS

FILL IN ALL PERTINENT INFORMATION REQUESTED AND MAIL ORIGINAL TO STATE  
DEPARTMENT OF PUBLIC HEALTH CONSUMER HEALTH PROTECTION 535 WEST  
JEFFERSON SPRINGFIELD ILLINOIS 62761 DO NOT DETACH GEOLOGICAL/WATER  
SURVEYS SECTION BE SURE TO PROVIDE PROPER WELL LOCATION.

## ILLINOIS DEPARTMENT OF PUBLIC HEALTH WELL CONSTRUCTION REPORT

### Type of Well

- a Dug \_\_\_\_\_ Bored \_\_\_\_\_ Hole Diam \_\_\_\_\_ in Depth \_\_\_\_\_ ft  
Curb material \_\_\_\_\_ Buried Slab Yes \_\_\_\_\_ No \_\_\_\_\_  
b Driven \_\_\_\_\_ Drive Pipe Diam \_\_\_\_\_ in Depth \_\_\_\_\_ ft  
c Drilled ☒ Finished in Drift \_\_\_\_\_ in Rock ☒  
Tabular \_\_\_\_\_ Gravel Packed \_\_\_\_\_  
d Grout \_\_\_\_\_

(KIND)	FROM (FT)	TO (FT)


2. Distance to Nearest  
Building 22 Ft. Seepage Tile Field 100  
Cess Pool \_\_\_\_\_ Sewer (non Cast iron) \_\_\_\_\_  
Privy \_\_\_\_\_ Sewer (Cast iron) 100  
Septic Tank 7.5 Barnyard \_\_\_\_\_  
Leaching Pit \_\_\_\_\_ Manure Pile \_\_\_\_\_  
3. Well furnishes water for human consumption? Yes ☒ No \_\_\_\_\_  
4. Date well completed Dec. 3 - 1986  
5. Permanent Pump Installed? Yes ☒ Date Dec 3, 1986 No \_\_\_\_\_  
Manufacturer Red Rocket Type Sub Location In Well  
Capacity 12 gpm. Depth of Setting 140 Ft  
6. Well Top Sealed? Yes ☒ No \_\_\_\_\_ Type Martinsen  
7. Pitless Adapter Installed? Yes ☒ No \_\_\_\_\_  
Manufacturer Martinsen Model Number B P 10  
How attached to casing? Threaded Nut  
8. Well Disinfected? Yes ☒ No \_\_\_\_\_  
9. Pump and Equipment Disinfected? Yes ☒ No \_\_\_\_\_  
10. Pressure Tank Size 20 gal Type Well x-Frol  
Location In Basement  
11. Water Sample Submitted? Yes ☒ No \_\_\_\_\_

REMARKS.

Co # 26301

## GEOLOGICAL AND WATER SURVEYS WELL RECORD

10. Proper \_\_\_\_\_ non-responsive  
Address \_\_\_\_\_  
Driller Jack Bull License No. 92-606  
11. Permit No 128281 Date Nov. 25, 1986  
12. Water from Rock 13. County Winneshago  
at depth 120 to 265 ft Sec 11.50  
14. Screen Diam \_\_\_\_\_ in Twp 26N  
Length \_\_\_\_\_ ft Slot \_\_\_\_\_ Rge 11E  
Elev \_\_\_\_\_



### 15 Casing and Liner Pipe

Diam. (in.)	Kind and Weight	From (Ft)	To (Ft)
<u>5</u>	<u>258 Black</u>	<u>0</u>	<u>42</u>

SHOW  
LOCATION IN  
SECTION PLAT

SE NE SW

16. Size Hole below casing 5 in  
17. Static level 120 ft below casing top which is 10 in above ground level  
Pumping level 125 ft when pumping at 12 gpm for 6 hours

18 FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
<u>Top Soil</u>	<u>0</u>	<u>5</u>
<u>Clay, Gravel</u>	<u>5</u>	<u>3.5</u>
<u>yellow limestone</u>	<u>3.5</u>	<u>16.5</u>
<u>Gray Rock</u>	<u>16.5</u>	<u>220</u>
<u>St. Pete</u>	<u>220</u>	<u>265</u>

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED Jack Bull DATE 1-15-87

White Copy - Well Owner  
Yellow Copy - Well Contractor  
Blue Copy - Well Owner

# INSTRUCTIONS TO DRILLERS

FILL IN ALL PERTINENT INFORMATION DU ED AND MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH ROOM 16, STATE OFFICE BUILDING SPRINGFIELD ILLINOIS 62706 DO NOT DETACH GEOLOGICAL / WATER SURVEYS SECTION BE SURE TO PROVIDE PROPER WELL LOCATION

1/67

## ILLINOIS DEPARTMENT OF PUBLIC HEALTH WELL CONSTRUCTION REPORT

### 1 Type of Well

- a Dug ☐ Bored ☐ Hole Diam 1 in Depth 35 ft  
Curb material            Buried Slab Yes ☐ No ☐
- b Driven ☐ Drive Pipe Diam            in Depth            ft
- c Drilled ☒ Finished in Drift ☐ In Rock ☒  
Tubular ☐ Gravel Packed ☐
- d Grout ☐

(KIND)	FROM (FT)	TO (FT)
CLAY	0	35
GRAVEL	35	140

### 2 Distance to Nearest

Building 15 Ft Seepage Tile Field 130  
Cess Pool            Sewer (non Cast iron)             
Privy            Sewer (Cast iron)             
Septic Tank 165 Barnyard             
Leaching Pit            Manure Pile           

### 3 Is water from this well to be used for human consumption?

Yes ☒ No ☐

### 4 Date well completed 12/15/71

5 Permanent Pump Installed? Yes ☒ No ☐  
Manufacturer JOHN DEERE Type 50341610  
Capacity            gpm Depth of setting 105 ft

### 6 Well Top Sealed? Yes ☒ No ☐

### 7 Pitless Adaptor Installed? Yes ☒ No ☐

### 8 Well Disinfected? Yes ☒ No ☐

### 9 Water Sample Submitted? Yes ☒ No ☐

REMARKS

## GEOLOGICAL WATER SURVEYS WATER WELL RECORD

10 Dept Mines and Minerals permit No 12715 Year 1971

11 Property            non-responsive

Address           

Driller            License No 22-214


12 Water from            13 County           

at depth 260 to 308 ft

14 Screen Diam            in

Length            ft Slot           

Sec 14-1  
Twp 17N  
Rng 1E  
Elev           



### 15 Casing and Liner Pipe

Diam (in)	Kind and Weight	From (Ft)	To (Ft)
6	Dr. 12.5" 40	0	110

SHOW LOCATION IN SECTION PLAT  
NW/4 NW  
116 SC

16 Size Hole below casing 6 in

17 Static level 26 ft below casing top which is 1 ft above ground level  
Pumping level 26 ft when pumping at 100 gpm for 2 hours

18 FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
CLAY	31	1
GRAVEL	31	31
CLAY	12	43
STATION SAND	41	84
(CONTINUE ON SEPARATE SHEET IF NECESSARY)		

SIGNED            DATE 12/15/71

White Copy  
Ill Dept of Public Health  
Yellow Copy - Well Contractor  
Blue Copy - Well Owner

FILL IN ALL PERTINENT INFORMATION REQUESTED AND MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH ROOM 616 STATE OFFICE BUILDING SPRINGFIELD ILLINOIS 62706 DO NOT DETACH GEOLOGICAL / WATER SURVEYS SECTION BE SURE TO PROVIDE PROPER WELL LOCATION

# ILLINOIS DEPARTMENT OF PUBLIC HEALTH WELL CONSTRUCTION REPORT

## 1 Type of Well

- a Dug \_\_\_\_\_ Bored \_\_\_\_\_ Hole Diam \_\_\_\_\_ in Depth \_\_\_\_\_ ft  
Curb material \_\_\_\_\_ Buried Slab Yes \_\_\_\_\_ No \_\_\_\_\_
- b Driven \_\_\_\_\_ Drive Pipe Diam \_\_\_\_\_ in Depth \_\_\_\_\_ ft
- c Drilled ☒ Finished in Drift \_\_\_\_\_ In Rock ☒  
Tubular \_\_\_\_\_ Gravel Packed \_\_\_\_\_
- d Grout

(KIND)	FROM (Ft)	TO (Ft)

Distance to Nearest

Building 20 Ft Seepage Tile Field 80  
Cess Pool \_\_\_\_\_ Sewer (non Cast iron) \_\_\_\_\_  
Privy \_\_\_\_\_ Sewer (Cast iron) \_\_\_\_\_  
Septic Tank 60 Barnyard \_\_\_\_\_  
Leaching Pit \_\_\_\_\_ Manure Pile \_\_\_\_\_

## 3 Is water from this well to be used for human consumption?

Yes ☒ No \_\_\_\_\_4 Date well completed Dec. 7-685 Permanent Pump Installed? Yes \_\_\_\_\_ No ☒

Manufacturer \_\_\_\_\_ Type \_\_\_\_\_

Capacity \_\_\_\_\_ gpm Depth of setting \_\_\_\_\_ ft

6 Well Top Sealed? Yes ☒ No \_\_\_\_\_7 Pitless Adaptor Installed? Yes \_\_\_\_\_ No ☒8 Well Disinfected? Yes ☒ No \_\_\_\_\_9 Water Sample Submitted? Yes \_\_\_\_\_ No ☒

REMARKS

Somebody Else put pump in

## GEOLOGICAL WATER SURVEYS WATER WELL RECORD

10 Dept Mines and Minerals permit No. 12345 Year 196811 Property **non-responsive**

Address \_\_\_\_\_

Driller C. L. Motter License No. 42-33512 Water from Formation 13 County WINNEBAGOat depth 60 to 150 ft Sec 147g14 Screen Diam \_\_\_\_\_ in Twp 26NLength \_\_\_\_\_ ft Slot \_\_\_\_\_ Rng 11E

Elev \_\_\_\_\_

## 15 Casing and Liner Pipe

Diam (in)	Kind and Weight	From (Ft)	To (Ft)	SHOW LOCATION OF SECTION PL.
<u>6</u>	<u>Steel 19.45</u>	<u>0</u>	<u>60 1/2</u>	<u>SE NW</u>
				<u>NW</u>

16 Size Hole below casing 6 in17 Static level 30 ft below casing top which is 1  
above ground level Pumping level 45 ft when pumping at 14  
gpm for 1 hours

18 FORMATIONS PASSED THROUGH	THICKNESS	DEPTH (BOTTOM)
<u>Black Lamin</u>	<u>2</u>	<u>2</u>
<u>Sandy Brown Clay</u>	<u>23</u>	<u>25</u>
<u>Sand &amp; Gravel</u>	<u>5</u>	<u>30</u>
<u>Blue Clay</u>	<u>20</u>	<u>50</u>
<u>Sandy Blue Clay</u>	<u>10</u>	<u>60</u>
<u>Yellow Limestone</u>	<u>60</u>	<u>120</u>
<u>Blue " "</u>	<u>25</u>	<u>145</u>
<u>Blue Limestone</u>	<u>5</u>	<u>150</u>
(CONTINUE ON SEPARATE SHEET IF NECESSARY)		

SIGNED C. L. Motter DATE Dec. 9-68

ILLINOIS DEPARTMENT OF PUBLIC HEALTH  
WELL CONSTRUCTION REPORT

1 Type of Well

- a Dug \_\_\_\_\_ Bored \_\_\_\_\_ Hole Diam 6 in Depth 154 ft  
Curb material \_\_\_\_\_ Buried Slab Yes \_\_\_\_\_ No \_\_\_\_\_  
b Driven \_\_\_\_\_ Drive Pipe Diam 6 in Depth 21 ft  
c Drilled \_\_\_\_\_ Finished in Drift \_\_\_\_\_ In Rock X  
Tubular \_\_\_\_\_ Gravel Packed \_\_\_\_\_  
d Grout \_\_\_\_\_

(KIND)	FROM (Ft)	TO (Ft)

2 Distance to Nearest

Building 6 Ft Seepage Tile Field 100  
Cess Pool \_\_\_\_\_ Sewer (non Cast iron) \_\_\_\_\_  
Privy \_\_\_\_\_ Sewer (Cast iron) X  
Septic Tank 75 Barnyard \_\_\_\_\_  
Leaching Pit \_\_\_\_\_ Manure Pile \_\_\_\_\_

3 Is water from this well to be used for human consumption?

Yes Y No \_\_\_\_\_

4 Date well completed Jan 11, 1969

5 Permanent Pump Installed? Yes Y No \_\_\_\_\_

Manufacturer Miller Type Electric  
Capacity 1 gpm Depth of setting 154 ft

6 Well Top Sealed? Yes Y No \_\_\_\_\_

7 Pitless Adaptor Installed? Yes Y No \_\_\_\_\_

8 Well Disinfected? Yes Y No \_\_\_\_\_

9 Water Sample Submitted? Yes \_\_\_\_\_ No X

REMARKS

GEOLOGICAL WATER SURVEYS WATER WELL RECORD

10 Dept Mines and Minerals Report No. 7445 Year 1969

11 Property non-responsive

Address \_\_\_\_\_

Driller James J. McLaughlin License No. 11 511

12 Water from Formation 13 County 11

at depth \_\_\_\_\_ to \_\_\_\_\_ ft Sec 11.4a

14 Screen Diam \_\_\_\_\_ in Twp 26N

Length \_\_\_\_\_ ft Slot \_\_\_\_\_ Rng 11E

Elev \_\_\_\_\_

15 Casing and Liner Pipe

Diam (in)	Kind and Weight	From (Ft)	To (Ft)
<u>6</u>		<u>Top</u>	<u>21</u>

SHOW  
LOCATION IN  
SECTION PL  
SW SW S

16 Size Hole below casing 6 in

17 Static level 70 ft below casing top which is \_\_\_\_\_

above ground level Pumping level 70 ft when pumping at \_\_\_\_\_

gpm for 1 hours

18 FORMATIONS PASSED THROUGH	THICKNESS	DEPTH (BOTTO)
<u>top clay</u>	<u>60</u>	<u>60</u>
<u>sand and clay</u>	<u>16</u>	<u>76</u>
<u>yellow limestone</u>	<u>40</u>	<u>116</u>
<u>gray limestone</u>	<u>34</u>	<u>150</u>

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED \_\_\_\_\_ DATE \_\_\_\_\_



White Copy -  
Ill Dept of Public Health  
Yellow Copy - Well Contractor  
Blue Copy - Well Owner

# INSTRUCTIONS TO F LERS

FILL IN ALL PERTINENT INFORMATION REQUESTED AND MAIL ORIGINAL TO STATE  
DEPARTMENT OF PUBLIC HEALTH BUREAU OF ENVIRONMENTAL HEALTH 535 WEST  
JEFFERSON SPRINGFIELD ILLINOIS 62701 DO NOT DETACH GEOLOGICAL/WATER  
SURVEYS SECTION BE SURE TO PROVIDE PROPER WELL LOCATION

## ILLINOIS DEPARTMENT OF PUBLIC HEALTH WELL CONSTRUCTION REPORT

### 1 Type of Well

- a Dug ☐ Bored ☐ Hole Diam ☐ in Depth ☐ ft  
Curb material ☐ Buried Slab Yes ☐ No ☐  
b Driven ☐ Drive Pipe Diam ☐ in Depth ☐ ft  
c Drilled ☒ Finished in Drift ☒ In Rock ☐  
Tubular ☐ Gravel Packed ☐  
d Grout

(KIND)	FROM (Ft)	TO (Ft)
none		

### 2 Distance to Nearest

Building 12 Ft Seepage Tile Field 100  
Cess Pool ☐ Sewer (non Cast iron) ☐  
Privy ☐ Sewer (Cast iron) ☐  
Septic Tank 50 Barnyard ☐  
Leaching Pit ☐ Manure Pile ☐

### 3 Is water from this well to be used for human consumption?

Yes ☒ No ☐

### 4 Date well completed Apr 1 8

### 5 Permanent Pump Installed? Yes ☒ No ☐

Manufacturer Sta-Rite Type 5-bm  
Capacity 10 gpm Depth of setting 30 ft

### 6 Well Top Sealed? Yes ☒ No ☐

### 7 Pitless Adaptor Installed? Yes ☒ No ☐

### 8 Well Disinfected? Yes ☒ No ☐

### 9 Water Sample Submitted? Yes ☒ No ☐

### REMARKS

Water sample reported  
safe By Winnebago Co  
Health Dept.

IDPH 4 065

10-72

1

## GEOLOGICAL AND WATER SURVEYS WELL RECORD

### 10 Property owner non-responsive

Address Ed Greenfield

Driller Ed Greenfield License No 92582

11 Permit No 28231 Date March 20


12 Water from Sand 13 County Win.

Formation  
at depth 40 to 42 ft Sec 14

14 Screen Diam 4 in Twp 26N

Length 2 ft Slot 15 Rge 11E

Elev ☐



### 15 Casing and Liner Pipe

Diam (in)	Kind and Weight	From (Ft)	To (Ft)
4	Blk PE 11# ft.	0	40
4	Johnson 15 screen	40	42

SHOW  
LOCATION IN  
SECTION PLAT  
100' N 100' W  
safe sense SE

### 16 Size Hole below casing ☐ in

17 Static level 15 ft below casing top which is 1 ft  
above ground level Pumping level 21 ft when pumping at 10  
gpm for 8 hours

18 FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
<u>Soil</u>	<u>2</u>	<u>2</u>
<u>Sandy clay</u>	<u>30</u>	<u>32</u>
<u>sand</u>	<u>10</u>	<u>42</u>

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED Ed Greenfield DATE May 8

## INSTRUCTION IS TO FILERS

White Copy -  
Ill Dept of Public Health  
Yellow Copy - the Contractor  
Blue Copy - Well Owner

FILL IN ALL PERTINENT INFORMATION REQUESTED AND MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH ROOM 616 STATE OFFICE BUILDING SPRINGFIELD ILLINOIS 62706 DO NOT DETACH GEOLOGICAL/WATER SURVEYS SECTION BE SURE TO PROVIDE PROPER WELL LOCATION

# ILLINOIS DEPARTMENT OF PUBLIC HEALTH WELL CONSTRUCTION REPORT

## 1 Type of Well

- a Dug \_\_\_\_\_ Bored \_\_\_\_\_ Hole Diam 9 in Depth 41 ft  
Curb material \_\_\_\_\_ Buried Slab Yes \_\_\_\_\_ No \_\_\_\_\_  
b Driven \_\_\_\_\_ Drive Pipe Diam 4 in Depth 41 ft  
c Drilled X Finished in Drift \_\_\_\_\_ In Rock X  
Tubular \_\_\_\_\_ Gravel Packed \_\_\_\_\_  
d Grout

(KIND)	FROM (Ft)	TO (Ft)
Grout	1	41

## 2 Distance to Nearest

- Building 75 Ft Seepage Tile Field 75  
Cess Pool \_\_\_\_\_ Sewer (non Cast iron) \_\_\_\_\_  
Privy \_\_\_\_\_ Sewer (Cast iron) \_\_\_\_\_  
Septic Tank 1 Barnyard \_\_\_\_\_  
Leaching Pit \_\_\_\_\_ Manure Pile \_\_\_\_\_

## 3 Is water from this well to be used for human consumption?

Yes X No \_\_\_\_\_

4 Date well completed 2/3/72

- 5 Permanent Pump Installed? Yes X No \_\_\_\_\_  
Manufacturer 6-1/2 Type 1/2  
Capacity \_\_\_\_\_ gpm Depth of setting 36 ft

6 Well Top Sealed? Yes X No \_\_\_\_\_7 Pitless Adaptor Installed? Yes X No \_\_\_\_\_8 Well Disinfected? Yes X No \_\_\_\_\_9 Water Sample Submitted? Yes X No \_\_\_\_\_

## REMARKS

## GEOLOGICAL AND WATER SURVEYS WELL RECORD

## 10 Property of

Address

Driller

License No

11 Permit No 16237

Date

12 Water from Rock

13 County

Formation

at depth \_\_\_\_\_ to \_\_\_\_\_ ft

Sec

## 14 Screen Diam \_\_\_\_\_ in

Twp

Length \_\_\_\_\_ ft Slot \_\_\_\_\_

Rge

Elev \_\_\_\_\_

## 15 Casing and Liner Pipe

Diam (in)	Kind and Weight	From (Ft)	To (Ft)
6	Black steel		

SHOW  
LOCATION IN  
SECTION PLAT  
NE NE SW

16 Size Hole below casing 6 in

- 17 Static level 45 ft below casing top which is 1 ft  
above ground level Pumping level 60 ft when pumping at 10  
gpm for 2 hours

18 FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
top soil	1	1
clay	8	9
fine sand	6	15
rock	7.7	42

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED

DATE

White Copy  
Ill Dept of Public Health  
Yellow Copy - Well Contractor  
Blue Copy - Well Owner

# INSTRUCTIONS TO WELLERS

FILL IN ALL PERTINENT INFORMATION REQUIRED AND MAIL ORIGINAL TO STATE  
DEPARTMENT OF PUBLIC HEALTH CONSUMER HEALTH PROTECTION 535 WEST  
JEFFERSON SPRINGFIELD ILLINOIS 62761 DO NOT DETACH GEOLOGICAL/WATER  
SURVEYS SECTION BE SURE TO PROVIDE PROPER WELL LOCATION

## ILLINOIS DEPARTMENT OF PUBLIC HEALTH WELL CONSTRUCTION REPORT

### 1 Type of Well

- a Dug \_\_\_\_\_ Bored \_\_\_\_\_ Hole Diam \_\_\_\_\_ in Depth \_\_\_\_\_ ft  
Curb material \_\_\_\_\_ Buried Slab Yes \_\_\_\_\_ No \_\_\_\_\_  
b Driven \_\_\_\_\_ Drive Pipe Diam \_\_\_\_\_ in Depth \_\_\_\_\_ ft  
c Drilled \_\_\_\_\_ Finished in Drift \_\_\_\_\_ In Rock \_\_\_\_\_  
Tubular \_\_\_\_\_ Gravel Packed \_\_\_\_\_  
d Grout \_\_\_\_\_

(KIND)	FROM (Ft)	TO (Ft)

### 2 Distance to Nearest

Building 30 Ft Seepage Tile Field 100  
Cess Pool \_\_\_\_\_ Sewer (non Cast iron) \_\_\_\_\_  
Privy \_\_\_\_\_ Sewer (Cast iron) \_\_\_\_\_  
Septic Tank 75 Barnyard \_\_\_\_\_  
Leaching Pit \_\_\_\_\_ Manure Pile \_\_\_\_\_

3 Well furnishes water for human consumption? Yes ☒ No \_\_\_\_\_

4 Date well completed 12-15-86

5 Permanent Pump Installed? Yes ☒ Date 12-15-86 No \_\_\_\_\_

Manufacturer RED JACKET Type SUB Location WELL  
Capacity 8 gpm Depth of Setting 145 Ft.

6 Well Top Sealed? Yes ☒ No \_\_\_\_\_ Type LP-5

7 Pitless Adapter Installed? Yes ☒ No \_\_\_\_\_

Manufacturer MARTISON Model Number BP-10

How attached to casing? WUT

8 Well Disinfected? Yes ☒ No \_\_\_\_\_

9 Pump and Equipment Disinfected? Yes ☒ No \_\_\_\_\_

10 Pressure Tank Size 20 gal Type WELLXTRAL 202

Location BASEMENT

11 Water Sample Submitted? Yes ☒ No \_\_\_\_\_

### REMARKS

Winn 960 5142 C # 26264  
7273 Cunningham RD

## GEOLOGICAL AND WATER SURVEYS WELL RECORD

### 10 Property

Address \_\_\_\_\_

Driller JESSIE BEAMAN License No. 92-599

11 Permit No 127538 Date 10-23-86

12 Water from SANDSTONE 13 County WINN

Formation \_\_\_\_\_ at depth 260 to 280 ft

14 Screen Diam \_\_\_\_\_ in Twp 26N

Length \_\_\_\_\_ ft Slot \_\_\_\_\_ Rge 1E

Elev \_\_\_\_\_

### 15 Casing and Liner Pipe

Diam. (in)	Kind and Weight	From (Ft)	To (Ft)
<u>5</u>	<u>13.00 BLACK</u>	<u>0</u>	<u>73</u>

SHOW  
LOCATION IN  
SECTION PLAT

NE NW NW

16 Size Hole below casing 5 in

17 Static level 105 ft below casing top which is 1 ft  
above ground level Pumping level 120 ft when pumping at 10  
gpm for 2 hours

18 FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
<u>CLAY</u>	<u>40</u>	<u>40</u>
<u>GRAVEL</u>	<u>20</u>	<u>63</u>
<u>CLAY</u>	<u>10</u>	<u>73</u>
<u>LIME STONE</u>	<u>187</u>	<u>260</u>
<u>SANDSTONE</u>	<u>20</u>	<u>280</u>

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED Jessie Beaman DATE 3-21-87



White Copy  
Ill Dept Public Health  
Yellow Copy - Well Contractor  
Blue Copy - Well Owner

# INSTRUCTIONS TO DRILLERS

FILL IN ALL PERTINENT INFORMATION REGISTERED AND MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH ROOM 616 STATE OFFICE BUILDING SPRINGFIELD ILLINOIS 62706 DO NOT DETACH GEOLOGICAL / WATER SURVEYS SECTION BE SURE TO PROVIDE PROPER WELL LOCATION

1/67

## ILLINOIS DEPARTMENT OF PUBLIC HEALTH WELL CONSTRUCTION REPORT

### 1 Type of Well

- a Dug \_\_\_\_\_ Bored \_\_\_\_\_ Hole Diam \_\_\_\_\_ in Depth \_\_\_\_\_ ft  
Curb material \_\_\_\_\_ Buried Slab Yes \_\_\_\_\_ No \_\_\_\_\_
- b Driven \_\_\_\_\_ Drive Pipe Diam \_\_\_\_\_ in Depth \_\_\_\_\_ ft
- c Drilled ☒ Finished in Drift \_\_\_\_\_ In Rock ☒  
Tubular \_\_\_\_\_ Gravel Packed \_\_\_\_\_
- d Grout

(KIND)	FROM (Ft)	TO (Ft)

### 2 Distance to Nearest

Building 20 Ft Seepage Tile Field 80  
Cess Pool \_\_\_\_\_ Sewer (non Cast iron) \_\_\_\_\_  
Privy \_\_\_\_\_ Sewer (Cast iron) \_\_\_\_\_  
Septic Tank 60 Barnyard \_\_\_\_\_  
Leaching Pit \_\_\_\_\_ Manure Pile \_\_\_\_\_

### 3 Is water from this well to be used for human consumption?

Yes ☒ No \_\_\_\_\_

### 4 Date well completed Dec 7-68

5 Permanent Pump Installed? Yes \_\_\_\_\_ No ☒  
Manufacturer \_\_\_\_\_ Type \_\_\_\_\_  
Capacity \_\_\_\_\_ gpm Depth of setting \_\_\_\_\_ ft

6 Well Top Sealed? Yes ☒ No \_\_\_\_\_

7 Pitless Adaptor Installed? Yes \_\_\_\_\_ No ☒

8 Well Disinfected? Yes ☒ No \_\_\_\_\_

9 Water Sample Submitted? Yes \_\_\_\_\_ No ☒

### REMARKS

Somebody Else put pump in

## GEOLOGICAL WATER SURVEYS WATER WELL RECORD

- 10 Dept Mines and Minerals permit No 6365 Year 1968
- 11 Property non-responsive  
Address \_\_\_\_\_  
Driller C. L. Mott License No 42-335
- 12 Water from Limestone 13 County WINNEBAGO  
Formation  
at depth 60 to 150 ft Sec 147g  
14 Screen Diam \_\_\_\_\_ in Twp 26N  
Length \_\_\_\_\_ ft Slot \_\_\_\_\_ Rng 11E  
Elev \_\_\_\_\_


### 15 Casing and Liner Pipe

Diam (in)	Kind and Weight	From (Ft)	To (Ft)
<u>6</u>	<u>Steel 19.43</u>	<u>0</u>	<u>60 1/2</u>

SHOW LOCATION IN SECTION PLAT  
SE NW  
26N

16 Size Hole below casing 6 in

17 Static level 30 ft below casing top which is 1 ft  
above ground level Pumping level 45 ft when pumping at 14  
gpm for 1 hours

18 FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
<u>Black Limestone</u>	<u>2</u>	<u>2</u>
<u>Sandy Brown Clay</u>	<u>23</u>	<u>25</u>
<u>Sand &amp; Gravel</u>	<u>5</u>	<u>30</u>
<u>Blue Clay</u>	<u>20</u>	<u>50</u>
<u>Sandy Blue Clay</u>	<u>10</u>	<u>60</u>
<u>Yellow Limestone</u>	<u>60</u>	<u>120</u>
<u>Blue " "</u>	<u>25</u>	<u>145</u>
<u>(CONTINUE ON SEPARATE SHEET IF NECESSARY)</u>	<u>5</u>	<u>150</u>

SIGNED C. Will. L. Mott DATE Dec. 9-68

IDPH 4 065  
1/74 - KNB 1

White Copy -  
Ill Dept of Public Health  
Yellow Copy - Well Contractor  
Blue Copy - Well Owner

# INSTRUCTIONS TO DRILLERS

FILL IN ALL PERTINENT INFORMATION REQUESTED AND MAIL ORIGINAL TO STATE  
DEPARTMENT OF PUBLIC HEALTH CONSUMER HEALTH PROTECTION 535 WEST  
JEFFERSON SPRINGFIELD ILLINOIS 62761 DO NOT DETACH GEOLOGICAL/WATER  
SURVEYS SECTION BE SURE TO PROVIDE PROPER WELL LOCATION

## ILLINOIS DEPARTMENT OF PUBLIC HEALTH WELL CONSTRUCTION REPORT

### 1 Type of Well

- a Dug ☐ Bored ☐ Hole Diam 5 in Depth 265 ft  
Curb material ☐ Buried Slab Yes ☐ No ☐  
b Driven ☐ Drive Pipe Diam ☐ in Depth ☐ ft  
c Drilled ☒ Finished in Drift ☐ In Rock ☒  
Tubular ☐ Gravel Packed ☐  
d Grout

(KIND)	FROM (Ft)	TO (Ft)

### 2 Distance to Nearest

- Building 125 Ft Seepage Tile Field 100  
Cess Pool ☐ Sewer (non Cast iron) ☐  
Privy ☐ Sewer (Cast iron) ☐  
Septic Tank 75 Barnyard ☐  
Leaching Pit ☐ Manure Pile ☐

### 3 Well furnishes water for human consumption? Yes ☒ No ☐

### 4 Date well completed 1-24-86

### 5 Permanent Pump Installed? Yes ☐ Date ☐ No ☐

- Manufacturer RED JACKET Type ☐ Location ☐  
Capacity ☐ gpm Depth of Setting ☐ Ft

### 6 Well Top Sealed? Yes ☒ No ☐ Type LP-5

### 7 Pitless Adapter Installed? Yes ☒ No ☐

- Manufacturer MARTIS Model Number BP-10  
How attached to casing? BOLTED

### 8 Well Disinfected? Yes ☒ No ☐

### 9 Pump and Equipment Disinfected? Yes ☒ No ☐

### 10 Pressure Tank Size ☐ gal Type ☐


Location ☐

### 11 Water Sample Submitted? Yes ☐ No ☐

### REMARKS

Winn - No - 4920

C # 25922



## GEOLOGICAL AND WATER SURVEYS WELL RECORD

### 10 Prop

Address **non-responsive**  
Driller JESSIE BEAMAN License No 92-599


### 11 Permit No 121147 Date 10-25-85

### 12 Water from SANDSTONE 13 County WINN

Formation  
at depth 245 to 265 ft Sec 1270

### 14 Screen Diam ☐ in Twp 26N

Length ☐ ft Slot ☐ Rge 11E  
Elev ☐



### 15 Casing and Liner Pipe

Diam (in)	Kind and Weight	From (Ft)	To (Ft)

SHOW  
LOCATION IN  
SECTION PLAT  
SE NW SW

### 16 Size Hole below casing ☐ in

### 17 Static level ☐ ft below casing top which is ☐ ft above ground level Pumping level ☐ ft when pumping at ☐ gpm for ☐ hours

18 FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
<u>CLAY</u>	<u>35</u>	<u>35</u>
<u>SAND</u>	<u>5</u>	<u>40</u>
<u>LIMESTONE</u>	<u>205</u>	<u>245</u>
<u>SAND STONE</u>	<u>20</u>	<u>265</u>

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED Jessie Beaman DATE ☐



INSTRUCTIONS TO DRILLERS

FILL IN ALL PERTINENT INFORMATION REQUESTED AND MAIL ORIGINAL TO STATE  
DEPARTMENT OF PUBLIC HEALTH CONSUMER HEALTH PROTECTION 535 WEST  
JEFFERSON SPRINGFIELD ILLINOIS 62761 DO NOT DETACH GEOLOGICAL/WATER  
SURVEYS SECTION BE SURE TO PROVIDE PROPER WELL LOCATION

ILLINOIS DEPARTMENT OF PUBLIC HEALTH  
WELL CONSTRUCTION REPORT

1 Type of Well

- a Dug \_\_\_\_\_ Bored \_\_\_\_\_ Hole Diam \_\_\_\_\_ in Depth \_\_\_\_\_ ft  
Curb material \_\_\_\_\_ Buried Slab Yes \_\_\_\_\_ No \_\_\_\_\_  
b Driven \_\_\_\_\_ Drive Pipe Diam \_\_\_\_\_ in Depth \_\_\_\_\_ ft  
c Drilled XX Finished in Drift \_\_\_\_\_ In Rock XX  
Tubular \_\_\_\_\_ Gravel Packed \_\_\_\_\_  
d Grout \_\_\_\_\_

(KIND)	FROM (Ft)	TO (Ft)
Drill cuttings	-0-	40'

2 Distance to Nearest

- Building 25 Ft Seepage Tile Field 100  
Cess Pool \_\_\_\_\_ Sewer (non Cast iron) \_\_\_\_\_  
Privv \_\_\_\_\_ Sewer (Cast iron) \_\_\_\_\_  
Septic Tank 85 Barnyard \_\_\_\_\_  
Leaching P t \_\_\_\_\_ Manure Pile \_\_\_\_\_

3 Well furnishes water for human consumption? Yes XX No \_\_\_\_\_

4 Date well completed 2/20/78

5 Permanent Pump Installed? Yes xx Date 2/21/78 No \_\_\_\_\_

Manufacturer Red Jacket Type sub Location well  
Capacity 15 gpm. Depth of Setting 100' Ft.

6 Well Top Sealed? Yes x No \_\_\_\_\_ Type LP-5

7 Pitless Adapter Installed? Yes y No \_\_\_\_\_

Manufacturer Mattinson Model Number BP-10  
How attached to casing? screw on

8 Well Disinfected? Yes x No \_\_\_\_\_

9 Pump and Equipment Disinfected? Yes XX No \_\_\_\_\_

10 Pressure Tank Size \_\_\_\_\_ gal Type Well-X-Trol 202  
Location basement

11 Water Sample Submitted? Yes \_\_\_\_\_ No xx

REMARKS

Lot # 65

Welden Hills Subd

GEOLOGICAL AND WATER SURVEYS WELL RECORD

10 Property

Address \_\_\_\_\_  
Driller Winifred McKinney License No 102-221

11 Permit No 70809 Date 1/18/78


12 Water from Rock 13 County Winnebago

Formation \_\_\_\_\_  
at depth 50 to 150 ft Sec 23.6

14 Screen Diam \_\_\_\_\_ in Twp 26N

Length \_\_\_\_\_ ft Slot \_\_\_\_\_ Rge 11E

Elev \_\_\_\_\_



15 Casing and Liner Pipe

Diam (in)	Kind and Weight	From (Ft)	To (Ft)
5"	Steel 15 lp.	-0-	40'

SHOW  
LOCATION IN  
SECTION PLAT

Lot 65, Welden  
Hills Subd,  
NW SE NW

16 Size Hole below casing 4 7/8 in

17 Static level 20 ft below casing top which is 1 ft  
above ground level Pumping level 40 ft when pumping at 30  
gpm for 2 hours

18 FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
Top soil	5	5'
Clay	10'	15'
Sand and gravel	5'	20'
Yellow limestone	25'	45'
Whitelimestone	50'	95'
Gray limestone	55'	150'

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED Winifred McKinney DATE 3-15-78

White Copy -  
Ill. Dep. of Public Health  
Yellow Copy - Well Contractor  
Blue Copy - Well Owner

INSTRUCTION TO DRILLERS

FILL IN ALL PERTINENT INFORMATION REQUESTED AND MAIL ORIGINAL TO STATE  
DEPARTMENT OF PUBLIC HEALTH CONSUMER HEALTH PROTECTION 535 WEST  
JEFFERSON SPRINGFIELD ILLINOIS 62761 DO NOT DETACH GEOLOGICAL/WATER  
SURVEYS SECTION BE SURE TO PROVIDE PROPER WELL LOCATION

ILLINOIS DEPARTMENT OF PUBLIC HEALTH  
WELL CONSTRUCTION REPORT

GEOLOGICAL AND WATER SURVEYS WELL RECORD

1 Type of Well

- a Dug \_\_\_\_\_ Bored \_\_\_\_\_ Hole Diam \_\_\_\_\_ in Depth \_\_\_\_\_ ft  
Curb material \_\_\_\_\_ Buried Slab Yes \_\_\_\_\_ No \_\_\_\_\_  
b Driven \_\_\_\_\_ Drive Pipe Diam \_\_\_\_\_ in Depth \_\_\_\_\_ ft  
c Drilled X Finished in Drift \_\_\_\_\_ In Rock X  
Tubular \_\_\_\_\_ Gravel Packed \_\_\_\_\_  
d Grout \_\_\_\_\_

(KIND)	FROM (Ft)	TO (Ft)

2 Distance to Nearest

Building 600 Ft Seepage Tile Field 600  
Cess Pool \_\_\_\_\_ Sewer (non Cast iron) \_\_\_\_\_  
Privy \_\_\_\_\_ Sewer (Cast iron) \_\_\_\_\_  
Septic Tank 610 Barnyard \_\_\_\_\_  
Leaching Pit \_\_\_\_\_ Manure Pile \_\_\_\_\_

3 Well furnishes water for human consumption? Yes \_\_\_\_\_ No X

4 Date well completed 7-1-85

5 Permanent Pump Installed? Yes \_\_\_\_\_ Date \_\_\_\_\_ No X

Manufacturer \_\_\_\_\_ Type \_\_\_\_\_ Location \_\_\_\_\_

Capacity \_\_\_\_\_ gpm Depth of Setting \_\_\_\_\_ Ft

6 Well Top Sealed? Yes \_\_\_\_\_ No \_\_\_\_\_ Type \_\_\_\_\_

7 Pitless Adapter Installed? Yes \_\_\_\_\_ No X

Manufacturer \_\_\_\_\_ Model Number \_\_\_\_\_

How attached to casing? \_\_\_\_\_

8 Well Disinfected? Yes \_\_\_\_\_ No \_\_\_\_\_

9 Pump and Equipment Disinfected? Yes \_\_\_\_\_ No \_\_\_\_\_

10 Pressure Tank Size \_\_\_\_\_ gal Type \_\_\_\_\_

Location \_\_\_\_\_

11 Water Sample Submitted? Yes \_\_\_\_\_ No \_\_\_\_\_

REMARKS WEAK FOR WIND MILL FOR

STOCK POUND

Co # 25793

COUNTY 4804

10 Proper

Address \_\_\_\_\_

Driller J Hinkle License No 102-187

11 Permit No 118353 Date 6-14-85

12 Water from ROCK 13 County WINN


Formation \_\_\_\_\_

at depth 40 to 125 ft Sec 21C

14 Screen Diam \_\_\_\_\_ in Twp 26N

Length \_\_\_\_\_ ft Slot \_\_\_\_\_ Rge 11E

Elev \_\_\_\_\_



15 Casing and Liner Pipe

Diam (in)	Kind and Weight	From (Ft)	To (Ft)
<u>5</u>	<u>T+C</u>	<u>0</u>	<u>37</u>

SHOW  
LOCATION IN  
SECTION PLAT

Lot #7  
West Houghton Subd  
SE NE SE

16 Size Hole below casing 5 in

17 Static level 50 ft below casing top which is 1 ft

above ground level Pumping level 50 ft when pumping at 10

gpm for 4 hours

18 FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
<u>TOP SOIL</u>	<u>5</u>	<u>5</u>
<u>CLAY LOAM</u>	<u>30</u>	<u>35</u>
<u>LIME ROCK</u>	<u>90</u>	<u>125</u>

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED Jamie A Hinkle DATE 7-1-85

